

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE
				ROADWAY
				0005
				URBAN
20200100	EARTH EXCAVATION	CU YD	50	50
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45
25100115	MULCH, METHOD 2	ACRE	0.5	0.5
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	660	660
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29.7	29.7
40600300	AGGREGATE (PRIME COAT)	TON	143	143
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N70	TON	4467	4467
40600990	TEMPORARY RAMP	SQ YD	1513	1513
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	6701	6701
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	94983	94983
44200140	PAVEMENT PATCHING, TYPE I, 12 INCH	SQ YD	4	4

FILE NAME =	USER NAME = harbaughd	DESIGNED -	REVISED -
c:\pwork\pwork\harbaugh\d\0349189\76g60.sht-S00.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -
MODEL NAME =	PLOT DATE = 1/31/2014		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NA SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8956	(59.60)RS-2	MADISON	27	4
CONTRACT NO. 76G60			ILLINOIS FED. AID PROJECT	