

RESURFACING SCHEDULE

LOCATION	HMA SURFACE REMOVAL 2.5" (SQ YD)	HMA SURFACE REMOVAL 1.5" (SQ YD)	HMA SURFACE REMOVAL 2.25" (SQ YD)	TEMPORARY RAMP (SQ YD)	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT (TON)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	STRIP REFL CRACK CONTROL TREATMENT (FT)	POLYMERIZED HMA SURF CSE MIX "D", N90 2.5" (TON)	LEVELING BINDER (MM) IL-9.5FG, N70 0.75" (TON)	HMA SURF CSE MIX "C", N70 1.5" (TON)	INCIDENTAL HMA SURFACING (TON)	HMA BASE CSE WIDENING 8" (SQ YD)	HMA SHOULDERS		HMA SHOULDERS 8"		AGGREGATE SHOULDER WEDGE TYPE B		
														LEFT SIDE (TON)	RIGHT SIDE (TON)	LEFT SIDE (SQ YD)	RIGHT SIDE (SQ YD)	LEFT SIDE (TON)	RIGHT SIDE (TON)	
LOC. NO. 1 - FAP 690																				
STA 12+50 TO 33+00	5466.67			70.90	1.71		8.20		765.33											
STA 33+00 TO 41+00	2640.00			46.67	0.83		3.96		369.60											
STA 41+00 TO 48+62	3208.87			53.90	1.00		4.81		449.24											
BRIDGE OMISSION																				
STA 51+38 TO 58+96	3145.70			53.22	0.98		4.72		440.40											
STA 58+96 TO 68+00	2843.58				0.89		4.27		398.10											
STA 68+00 TO 81+95	3720.00			22.20	1.16		5.58		520.80											
LOC. NO. 1 - FAS 819																				
STA 148+38 TO 190+62		11264.00		13.33		3.52	16.90	8448		473.09	948.48					1408.00	1408.00	52.57	52.57	
STA 190+62 TO 232+86		11264.00				3.52	16.90	8448		473.09	950.18					1408.00	1408.00	52.57	52.57	
STA 232+86 TO 268+24		9434.67				2.95	14.15	7076		396.26	797.21					1179.33	1179.33	44.03	44.03	
Addievilile Road		50.67				0.02	0.08					5.32								
STA 268+24 TO 287+93		5250.67				1.64	7.88	3938		220.53	441.36					656.33	656.33	24.50	24.50	
STA 287+93 TO 289+73		600.00				0.19	0.90	200		20.16	40.32			5.46	5.46				5.97	
STA 289+73 TO 307+84		4829.33				1.51	7.24	3622		202.83	407.26					603.67	603.67	22.54	22.54	
STA 307+84 TO 387+56		21258.67				6.65	31.89	15944		892.86	1788.53					2657.33	2657.33	99.21	99.21	
STA 387+56 TO 438+00		13450.67				4.21	20.18	10088		564.93	1131.16					1681.33	1681.33	62.77	62.77	
STA 438+00 TO 440+87		702.53		13.33		0.24	1.15	1150		32.19	64.38		255.47	8.72	8.72					
BRIDGE OMISSION																				
STA 443+52 TO 445+20		410.67		13.33		0.14	0.67	672		18.82	37.63		149.33	5.10	5.10					
STA 445+20 TO 507+95		16733.33				5.24	25.10	12550		702.80	1408.70					2091.67	2091.67	78.09	78.09	
STA 507+95 TO 574+59		17770.67				5.56	26.66	13328		746.37	1494.74					2221.33	2221.33	82.93	82.93	
STA 574+59 TO 578+59		1555.56		13.33		0.49	2.33	1400		87.11	130.67									
NORTH LEG OF IL 127		626.67		13.33		0.20	0.94	564		35.09	52.64									
SOUTH LEG OF IL 127		626.67		13.33		0.20	0.94	426		35.09	52.64									
LOC. NO. 2 - FAS 819																				
STA 85+00 TO 93+00			4088.89	20.00		1.28	6.13			97.07	194.13			112.00	112.00					
STA 93+00 TO 98+12		3413.33		22.20		1.07	5.12			95.57	191.15			71.68	71.68			6.37	6.37	
BRIDGE OMISSION																				
STA 102+61 TO 105+91		2199.67		37.80		0.69	3.30			61.59	123.18			46.19	46.19			4.11	4.11	
RAMP 1		3556.22		8.90		1.11	5.33			91.91	183.83			68.94	103.40			15.32	15.32	
RAMP 2		2123.33		8.90		0.66	3.19			54.88	109.76			41.16	61.74			9.15	9.15	
LOC. NO. 2 - FAP 322																				
RAMP 3		3775.78		8.90		0.73	3.49			97.59	195.18			73.19	109.79			16.26	16.26	
RAMP 4		2452.67		8.90		0.47	2.26			63.39	126.78			47.54	71.32			10.57	10.57	
TOTALS	21,025	133,350	4,089	442	7	42	234	87,854	2,943	5,463	10,870	5	405	480	595	13,907	13,907	581	587	
														1,075		27,814		1,168		

NOTE: THE QUANTITY FOR TEMPORARY RAMPS INCLUDES MATERIAL TO BE PLACED AT THE BEGINNING AND ENDS OF MILLED ROADWAY SECTIONS AND AT THE FOLLOWING SIDEROADS: TOWER DRIVE, EAST FRONTAGE ROAD, HEN HOUSE ROAD, RAMP D (TO EB I-64), AND RAMP A (TO WB I-64). TEMPORARY RAMPS AT THE I-64 RAMPS AND SIDEROADS SHALL NOT BE MORE THAN 3' IN LENGTH TO LIMIT ENCROACHMENT IN TRAFFIC LANES.

FILE NAME =	USER NAME = mlscmr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\p\dtd\mlscmr\d0345201\d876961-sht-pln.dgn		DRAWN -	REVISED -			•	(109,110)RS-1, 31-2RS	WASHINGTON	40	9	
		CHECKED -	REVISED -			•FAP 690/FAS 819/FAP 322					CONTRACT NO. 76G61
		DATE -	REVISED -			FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT			