

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS														
	SKIP-DASH YELLOW 4" (FT)	SOLID YELLOW 4" (FT)		SOLID WHITE 4" (FT)		SOLID YELLOW 4" (FT)	SOLID WHITE 8" (FT)	SOLID WHITE 12" (FT)	SOLID WHITE 24" (FT)	SOLID WHITE LETTERS & SYMBOLS (SQ FT)		PAINT CURB (FOOT)	PRISMATIC CURB REFLECTOR (EACH)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	
		CENTERLINE	NO PASSING ZONE		EDGE LINES	LANE LINE	MEDIAN EDGE LINE	ISLAND	ISLAND CHANNELIZATION	STOP BAR	LEFT TURN ARROW	"ONLY"	MEDIAN	MEDIAN	CRYSTAL ONE-WAY
	LT	RT													
LOC. NO. 1 - FAP 690															
STA. 12+50 TO 32+78	507			3931											26
STA. 32+78 TO 34+62	46		184	235											2
STA. 34+62 TO 42+72				1336		1467						84	30		
STA. 42+72 TO 45+97				640	300	654				46.8		42	16	8	
STA. 45+97 TO 48+62				530		538							13		
BRIDGE OMISSION															
STA. 51+38 TO 54+03				530		529								13	
STA. 54+03 TO 57+20				634	300	637				46.8		42	16	8	
STA. 57+20 TO 65+31				1332		1463						84	30		
STA. 65+31 TO 68+96	92	364		597											5
STA. 68+96 TO 81+95	325			2598											16
LOC. NO. 1 - FAS 819															
STA. 148+38 TO 287+19	3470			27763											174
STA. 287+19 TO 291+84	116		465	929											6
STA. 291+84 TO 300+76	223			1785											11
STA. 300+76 TO 306+30	139	554		1109											7
STA. 306+30 TO 440+87	3364			26913											168
BRIDGE OMISSION															
STA. 443+52 TO 452+93	235			1882											12
STA. 452+93 TO 458+42	137		549	1098											7
STA. 458+42 TO 464+76	158			1267											8
STA. 464+76 TO 470+20	136	544		1088											7
STA. 470+20 TO 470+35	4			32											
STA. 470+35 TO 480+02	242		966	1932											12
STA. 480+02 TO 481+60	40			317											2
STA. 481+60 TO 544+27	1567	6267		12535											78
STA. 544+27 TO 548+39	103			824											5
STA. 548+39 TO 557+90	238		950	1901											12
STA. 557+90 TO 559+32	36			285											2
STA. 559+32 TO 569+04	243	972		1943											12
STA. 569+04 TO 572+63	90			718											4
STA. 572+63 TO 574+59	49		200	392											2
IL 177/127 INTERSECTION	190	350	350	1328			200	60	124						8
LOC. NO. 2 - FAS 819															
STA. 85+00 TO 89+98				996		830									12
STA. 89+98 TO 97+12				1428		1428						84	36		
STA. 97+12 TO 98+12				200	107	200				15.6	20.8	42	6	3	
BRIDGE OMISSION															
STA. 102+61 TO 106+06				689	106	689				15.6	20.8	42	14	3	
RAMP 1				1231		1231			45			43			
RAMP 2				735		735									
LOC. NO. 2 - FAS 819															
RAMP 3				1307		1307			45			43			
RAMP 4				849		849									
SUBTOTALS	11749	9051	3664	105839	813	12557	200	60	214	124.8	41.6	506	174	22	599
TOTALS	143673						200	60	214	166		506	174	621	

NOTE: RAISED REFLECTIVE PAVEMENT MARKERS ARE NOT REQUIRED AT EDGELINES ADJACENT TO RAISED MEDIANS WHERE PRISMATIC CURB REFLECTORS ARE PRESENT.