

LOCATION SPECIFIC GENERAL NOTES

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS, COMMITMENTS & GENERAL NOTES
- 3-4 SUMMARY OF QUANTITIES
- 5-7 EXISTING STRUCTURE DETAILS (SN 060-0014 & 0015)
- 8-9 FRAMING PLAN (SN 060-0014 & 0015)
- 10-12 EXISTING STRUCTURE DETAILS (SN 060-0014 & 0015)
- 13-14 FRAMING PLAN (SN 060-0014 & 0015)
- 15 EXISTING STRUCTURE DETAILS (SN 082-0217, 0218)
- 16-17 EXISTING STRUCTURE DETAILS (SN 082-0217)
- 18 FRAMING PLAN (082-0217)
- 19-21 EXISTING STRUCTURE DETAILS (082-0218)
- 22 FRAMING PLAN (SN 082-0218)
- 23 EXISTING STRUCTURE DETAILS (SN 082-0217, 0218)
- 24-25 BEARING DETAILS (SN 082-0217, 0218)

GENERAL NOTES

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E (1-800-892-0123 OR 811) OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY.
2. UTILITY INTERFERENCES ARE NOT ANTICIPATED ON THIS CONTRACT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE HIS CONSTRUCTION ACTIVITIES WITH THE VARIOUS UTILITY OWNERS. ALL POTENTIAL CONFLICTS SHALL BE INVESTIGATED AND REMEDIAL ACTION TAKEN PRIOR TO INTERRUPTION OF THE CONTRACTOR'S PROGRESS. NO ADDITIONAL COST SHALL BE ADDED TO THE CONTRACT RESULTING FROM UTILITY CONFLICTS.
3. THE SSPC-OP1 AND SSPC-OP2 CERTIFICATIONS WILL BE REQUIRED FOR THE BRIDGE.
4. ALL TURF AREA DISTURBED BY THE CONTRACTOR SHALL BE SEEDED WITH THE APPROPRIATE EROSION CONTROL AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN AT THE CONTRACTOR'S EXPENSE.
5. THE USE OF CONES SHALL NOT BE PERMITTED ON THIS PROJECT.
6. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT EACH END OF THE PROJECT LOCATIONS AND ALL INTERSECTING SIDE ROADS AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE, 48".
7. CHANGEABLE MESSAGE SIGNS SHALL BE PLACED TWO (2) WEEKS PRIOR TO ANY LANE RESTRICTIONS AS DIRECTED BY THE RESIDENT ENGINEER/TECHNICIAN.
8. THE DEPARTMENT STRONGLY ENCOURAGES THE PRIME CONTRACTOR AND THEIR APPROVED SUB-CONTRACTORS TO HIRE MINORITY, WOMEN AND DISADVANTAGED INDIVIDUALS FROM ITS FEDERALLY FUNDED HIGHWAY CONSTRUCTION CAREERS TRAINING PROGRAM (HCCTP) TO HELP MEET WORKFORCE AND TRAINEE GOALS. THIS PROGRAM IS TRAINING MINORITIES, WOMEN AND DISADVANTAGED INDIVIDUALS IN HIGHWAY CONSTRUCTION-RELATED SKILLS, E.G., MATH FOR THE TRADES, JOB READINESS, TECHNICAL SKILLS COURSE WORK (CARPENTRY, CONCRETE FLATWORK, BLUEPRINT READING, SITE PLANS, SITE WORK, TOOLS USE, ETC.) AND OSHA 10 HOUR CERTIFICATION, TO PREPARE THEM FOR A CAREER IN THE HIGHWAY CONSTRUCTION TRADES. GRADUATES ARE WELL- TRAINED AND READY TO BECOME PRODUCTIVE ENTRY-LEVEL CONSTRUCTION WORKERS. CONTACT THE DISTRICT 8 EEO OFFICE AT 618-346-3360 AND/OR THE HCCTP COORDINATOR AT 618-874-6528 TO LEARN MORE ABOUT THE PROGRAM AND FOR ASSISTANCE IN MEETING WORKFORCE AND TRAINEE GOALS.

LOCATION 1

1. CLEANING AND PAINTING OF THE EXISTING STRUCTURAL STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES". ALL EXISTING STEEL SHALL BE CLEANED PER NEAR WHITE BLAST CLEANING- SSPC-SPI0. ALL EXISTING STEEL SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1-OZ/E/U. THE COLOR OF THE FINAL FINISH COAT FOR ALL STEEL SURFACES SHALL BE GRAY, MUNSELL NO 5B 7/1.
2. A MINIMUM OF TWO AIR MONITORS WILL BE REQUIRED AT SN 060-0014 AND SN 060-0015 TO MONITOR ABRASIVE BLASTING OPERATION, SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES."
3. EXISTING BEARINGS AND CATCH BEAMS THAT WERE PAINTED ON THE PREVIOUS CONTRACT ARE EXCLUDED FROM THIS CONTRACT. THE CONTRACTOR IS RESPONSIBLE FOR DAMAGE TO THE PAINT SYSTEM FOR THESE ITEMS THAT OCCURS DURING THE WORK BEING PERFORMED AS A PART OF THIS CONTRACT, AND THE CONTRACTOR IS RESPONSIBLE FOR CORRECTIVE MEASURES TO THE SATISFACTION OF THE RESIDENT ENGINEER/ TECHNICIAN.

LOCATION 2

1. CLEANING AND PAINTING OF THE EXISTING STEEL SHALL BE AS SPECIFIED IN THE SPECIAL PROVISION FOR "CLEANING AND PAINTING EXISTING STEEL STRUCTURES." ALL BEAMS, BEARINGS AND OTHER STEEL WITHIN 5 FT (MEASURED ALONG THE BEAM) OF EITHER SIDE OF DECK JOINTS SHALL BE CLEANED PER NEAR WHITE BLAST CLEANING - SSPC-SPI0.
2. THE DESIGNATED AREAS CLEANED PER NEAR WHITE BLAST CLEANING AND PER COMMERCIAL GRADE POWER TOOL CLEANING SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1-OZ/E/U. THE COLOR OF THE FINAL FINISH COAT FOR ALL CLEANED STEEL SHALL BE REDDISH BROWN, MUNSELL NO. 2.5YR 3/4.
3. A MINIMUM OF TWO AIR MONITORS WILL BE REQUIRED AT SN 082-0217 AND A MINIMUM OF TWO AIR MONITORS WILL BE REQUIRED AT SN 082-0218 TO MONITOR ABRASIVE BLASTING OPERATION, SEE SPECIAL PROVISIONS FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES."

STANDARDS

- 000001-06
- 001006
- 701106-02
- 701206-03
- 701400-07
- 701401-08
- 701406-08
- 701411-08
- 701606-09
- 701901-03
- 720001-01

COMMITMENTS

NONE

| | | | | | | | | | | | |
|-----------------------|----------------------|------------------|-----------------|---|--|---------------------------------|--|---------|--------------------|-------------------|--------------|
| FILE NAME * #FILE# | USER NAME * #USER# | DESIGNED - _____ | REVISED - _____ | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | INDEX OF SHEETS, GENERAL NOTES, HIGHWAY STANDARDS & COMMITMENTS | | F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | PLOT SCALE * #SCALE# | DRAWN - _____ | REVISED - _____ | | SCALE: N/A | SHEET NO. _____ OF _____ SHEETS | STA. _____ TO STA. _____ | 7666/7 | 82-THB-P, 60-THB-P | ST CLAIR, MADISON | 25 |
| | PLOT DATE * #DATE# | CHECKED - _____ | REVISED - _____ | | | | CONTRACT NO. 7664 | | | | |
| | | DATE - _____ | REVISED - _____ | | | | FED. ROAD DIST. NO. ILLINOIS/ED. AID PROJECT | | | | |