

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0014
				014-0058
50102400	CONCRETE REMOVAL	CU YD	87.9	87.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	87.4	87.4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13700	13700
50800515	BAR SPLICERS	EACH	88	88
52000110	PREFORMED JOINT STRIP SEAL	FOOT	228	228
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2860	2860
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2950	2950
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	954	954
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1475	1475

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE
				0014
				014-0058
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1475	1475
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2860	2860
78300100	PAVEMENT MARKING REMOVAL	SO FT	954	954
X5030530	FLOOR DRAIN EXTENSION	EACH	121	121
Z0015802	PLUG EXISTING DECK DRAINS	EACH	223	223
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	25	25
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	125	125

* SPECIALTY ITEM

FILE NAME =	USER NAME = dntslmanjn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\p\work\ps\dntslmanjn\0378447	0076091-shr-plan.dgn	DRAWN -	REVISED -		327	14-14B-1	CLINTON	27	3				
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT		
	PLOT DATE = 2/7/2014	DATE -	REVISED -										