

## PAVEMENT AND SHOULDER SCHEDULE

LOCATION			PROCESSING MODIFIED SOIL 12"	LIME	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE BASE COURSE, TYPE A 8"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH) 10 3/4"
STATION	TO	STATION	SO YD	TON	SO YD	SO YD	CU YD	SO YD	GAL	TON	TON	TON	TON	SO YD
<b>DONNA DRIVE</b>														
85+21.41	-	100+00.00	6566	162.5				6,446	5,239	31	871	520		
100+00.00	-	132+78.62	12866	318.4				12,368	10,272	61	1,666	994		
132+78.62	-	144+16.11							498	5			357	
<b>SARA LANE</b>														
8+20.00	-	10+00.00				508		487	344	2	64	38		
<b>MAIN STREET SOUTH</b>														
1+00.00	-	3+55.00	798	19.8			15		141	2				584
3+55.00	-	5+85.00	497	15.0			20							314
<b>MAIN STREET NORTH</b>														
0+00.00	-	15+07.50	5,439	134.6					796	13				4,423
0+65.22	-	0+75.76												
<b>PLAZA DRIVE EAST</b>														
126+47.01	-	126+72.01				79		77	54	0	9	5		
126+72.01	-	127+83.42				381		322	231	1	42	25		
<b>SAMUEL ROAD</b>														
6+00.00	-	10+90.00				1933		1,874	1,356	8	188	112		
15+42.43	-	17+24.52				966		946	689	4	105	62		
17+88.53	-	19+70.77				1029		993	724	4	113	67		
<b>BRIGGS ROAD</b>														
6+26.09	-	9+36.00	1,681	41.6				1,633	1,222	7	187	112		
10+00.00	-	11+48.74	723	17.9				714	499	3	79	47		
11+48.74	-	13+22.78	530	13.1				515	370	2	69	44		
<b>BRIGGS ROAD SPUR</b>														
100+00.00	-	102+70.00				825		794	562	3	105	63		
<b>SHEET TOTALS</b>			<b>29,100</b>	<b>723</b>	<b>0</b>	<b>5,721</b>	<b>35</b>	<b>27,169</b>	<b>22,998</b>	<b>149</b>	<b>3,497</b>	<b>2,089</b>	<b>357.3</b>	<b>5,321</b>
<b>SHEET TOTALS FROM PVMT SCH 01-02</b>			<b>72,218</b>	<b>1,787.0</b>	<b>80,383</b>	<b>2,241</b>	<b>860</b>	<b>27,728</b>	<b>22,492</b>	<b>256</b>	<b>3,724</b>	<b>2,225</b>	<b>644.5</b>	<b>28,494</b>
<b>SHEET TOTALS FROM DWY SCH-21</b>					<b>2,206</b>				<b>107</b>	<b>0</b>				
<b>SHEET TOTALS FROM DWY SCH-22</b>					<b>659</b>				<b>12</b>	<b>0</b>				
<b>PROJECT TOTALS</b>			<b>101,318</b>	<b>2,510.0</b>	<b>83,248</b>	<b>7,962</b>	<b>895</b>	<b>54,897</b>	<b>45,609</b>	<b>405</b>	<b>7,222</b>	<b>4,313</b>	<b>1,002</b>	<b>33,815</b>