

STORM SEWER SCHEDULE

LOCATION				STORM SEWERS, CLASS A													PRECAST REINFORCED CONCRETE FLARED END SECTIONS						CONCRETE COLLAR CU YD	POROUS GRANULAR BACKFILL CU YD	TRENCH BACKFILL CU YD	REMARKS
				TYPE 1					TYPE 2								12"	15"	18"	24"	30"	36"				
				12" FOOT	15" FOOT	18" FOOT	24" FOOT	30" FOOT	12" FOOT	15" FOOT	24" FOOT	30" FOOT	36" FOOT	42" FOOT	54" FOOT	72" FOOT										
STATION	TO	STATION	OFFSET	12" FOOT	15" FOOT	18" FOOT	24" FOOT	30" FOOT	12" FOOT	15" FOOT	24" FOOT	30" FOOT	36" FOOT	42" FOOT	54" FOOT	72" FOOT	12" EACH	15" EACH	18" EACH	24" EACH	30" EACH	36" EACH				
WOLF CREEK ROAD																										
83+16		83+26								117														30		
84+25		84+64							64															11		
83+36		84+25	LT						83															30		
83+16		83+36	LT						28															10		
83+11		83+16	LT							41								1						13		
85+51		87+43	LT						186															77		
87+43		88+00	LT						47								1							17		
91+50		92+00	RT						48															13		
92+00		92+46	RT						44															13		
92+46		92+81	RT						33															11		
92+81		92+86	RT						3															1		
92+86		92+86	RT						39								1							10		
93+25.50		93+30.50							3															2		
93+25.50		93+65							33															24		
93+65		94+00	LT						30															26		
94+00		94+51	LT						47															39		
93+65		93+65	LT						59								1							21		
NORTH FRONTAGE ROAD																										
22+60		25+03	RT						239															89		
22+60		22+60		31																				8		
25+03		26+40	RT								134													178		
26+40		26+40							38															11		
24+96		24+99	LT								26								1					23		
26+35		26+40	RT								20													26		
26+19		26+35	RT					22													1			23		
26+35		4+45						34																75		
24+96		25+03									35													39		
58+50		60+00	LT						140															47		
60+00		61+41	LT						132															53		
61+41		61+90	LT	42																				33		
61+90		63+00	LT						104															76		
63+00		65+00	LT						194															136		
65+00		67+00	LT						194															146		
111+31		112+00	LT						56															21		
112+00		112+00	LT					4													1			2		
112+00		113+00	LT						85															60		
111+88		112+00										74												73		
111+00		111+88	RT									91									1			108		
61+88		61+90	LT									27									1			27		
61+90		61+94.52										57									1			49		
69+30		69+30	LT					8													1			3		
69+30		70+00	LT					63													1			18		
108+50		109+25	RT	63																				19		
109+25		110+00	RT	70																				18		
111+88		112+56	RT										177											317		
112+56		573+48		81																		1		74		
69+18		69+30						55																13		
110+00		110+00	RT	16													1							4		
SHEET TOTALS				303	0	126	0	60	1,929	158	215	249	177	0	0	0	4	1	3	1	5	1	0.0	995	1,122	