

RIPRAP SCHEDULE

LOCATION				STONE DUMPED RIPRAP, CLASS A4	REMARKS
STATION	TO	STATION	LT/RT	TON	
IL 13					
488+29.27	-	489+50.53	LT	90	
489+22.48			RT	12	
502+77.90			RT	28	
503+00.00	-	503+96.19	LT	71	
503+92.24			RT	19	
506+00.00	-	507+00.00	LT	75	
506+56.56	-	507+61.00	RT	79	
519+16.80			RT	12	
521+97.05	-	523+24.68	RT	164	RAMP C INFIELD
535+78.59	-	536+50.00	LT	53	
537+71.99			RT	51	
540+38.97			RT	12	
543+00.00	-	543+34.51	RT	33	
543+34.51			RT	12	
546+50.00	-	547+26.62	LT	121	
547+03.07			RT	12	
553+91.54			LT	7	
557+57.45			RT	16	
559+67.06			RT	12	
567+90.54	-	569+78.13	LT	139	
572+13.20			RT	28	
571+91.62	-	573+53.02	LT	226	
573+58.88	-	575+45.36	LT	139	
575+08.76			RT	50	
576+41.74	-	580+00.00	LT	247	
577+79.22			RT	28	
583+80.00	-	584+16.63	LT	27	
584+16.40			RT	12	
590+34.88			LT	12	
RAMP A					
11+84.44			LT	12	
19+50.00			RT	12	
RAMP C					
11+28.23			RT	28	
19+62.02			RT	12	
RAMP D					
28+01.33			RT	38	
WOLF CREEK ROAD					
83+11.00			LT	7	
88+00.00			LT	3	
92+86.00			RT	3	
93+65.00			LT	3	
97+13.66	-	98+74.52	RT	161	RAMP A INFIELD
98+19.00			LT	3	
98+29.00			RT	36	
100+89.80	-	101+99.01	RT	110	RAMP D INFIELD
100+92.00			RT	31	
104+31.76	-	105+25.02	LT	42	
107+16.44			RT	47	
112+31.88			LT	5	
SUBTOTALS				2,338	

LOCATION				STONE DUMPED RIPRAP, CLASS A4	REMARKS
STATION	TO	STATION	LT/RT	TON	
WOLF CREEK ROAD (CONT'D)					
116+68.41			RT	5	
116+81.57			LT	7	
NORTH FRONTAGE ROAD					
61+94.00			RT	19	
69+18.34	-	69+51.82	RT	39	
74+90.00			LT	20	
74+90.00			RT	9	
80+50.00			LT	7	
80+50.00			LT	12	
94+51.44			LT	9	
94+63.00			RT	19	
99+40.00			RT	8	
99+40.00			RT	19	
105+93.69			RT	5	
106+47.64			LT	4	
106+80.29			RT	19	
110+00.00			RT	3	
FLEMING ROAD					
30+68.56			RT	12	
DONNA DRIVE					
95+98.33	-	96+77.08	RT	234	
96+41.96	-	97+50.64	LT	107	
108+64.10			LT	38	
113+47.59	-	114+01.30	RT	125	
121+61.24			LT	129	
121+61.24			RT	129	
125+09.00	-	125+42.00	LT	96	
128+27.43			RT	28	
128+92.83	-	129+54.31	RT	81	
130+74.83			RT	81	
MAIN STREET NORTH					
1+11.45			LT	10	
5+61.69	-	5+82.89	LT	25	
15+01.97			RT	3	
PLAZA DRIVE EAST					
127+19.14			RT	19	
SAMUEL ROAD					
10+29.60			LT	12	
19+66.71			RT	12	
BRIGGS ROAD					
12+73.70			RT	28	
SUBTOTALS				1,373	
PROJECT TOTALS				3,711	

FILE NAME =	USER NAME = \$USER\$	DESIGNED - KN	REVISED -
et:\pw\work\p\dot\lavenderba\d0363618\078221-sht-SCH-16.dgn		DRAWN - AS	REVISED -
	PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/31/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

RIPRAP SCHEDULE			
SCALE:	SHEET NO. 16 OF 56 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-3)R-2, N-4, T5-4, HBK-1	WILLIAMSON	733	58
DRAWING NO. SCH-16		CONTRACT NO. 78221		
<small>ILLINOIS FED. AID PROJECT</small>				