

## SIDEWALK SCHEDULE

LOCATION			PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH SO FT	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH SO FT	DETECTABLE WARNINGS SO FT	REMARKS
STATION	TO	STATION				
<b>WOLF CREEK ROAD</b>						
90+38.79	-	98+60.08		9,429.5	60.0	
100+75.92	-	103+25.70		2,695.5	20.0	
103+25.70	-	109+67.28		6,841.0	40.0	
<b>NORTH FRONTAGE ROAD</b>						
22+55.43	-	27+25.23		4,639.5	10.0	
27+25.23	-	28+01.14		579.0	10.0	
50+75.00	-	52+25.85		1,317.5	14.0	
52+25.85	-	53+83.13		1,198.0	14.0	
53+83.13	-	69+59.77		15,242.0	140.0	
69+59.77	-	74+40.74		4,872.0		
74+40.74	-	96+51.25		21,952.0	50.0	
96+51.25	-	97+02.92		1,250.0	200.0	
97+02.92	-	104+95.83		7,547.5	40.0	
104+95.83	-	111+62.48		6,560.5	20.0	
<b>MAIN STREET NORTH</b>						
5+84.08	-	14+78.52	3,880.5		10.0	
<b>PROJECT TOTALS</b>			<b>3,880.5</b>	<b>84,124.0</b>	<b>628.0</b>	