

# SIGNING SCHEDULE

LOCATION			SIGN PANEL - TYPE 1		SIGN PANEL - TYPE 2		SIGN PANEL - TYPE 3		POST (TYPE/LENGTH)			BASE FOR TELESCOPING STEEL SIGN SUPPORT EACH	WOOD SIGN SUPPORT FOOT	REMARKS
			PANEL SIZE IN X IN	TOTAL AREA SQ FT	PANEL SIZE IN X IN	TOTAL AREA SQ FT	PANEL SIZE IN X IN	TOTAL AREA SQ FT	METAL POST TYPE A FOOT	METAL POST TYPE B FOOT	TELESCOPING STEEL SIGN SUPPORT FOOT			
STATION	DETAIL	DESCRIPTION												
<b>IL 13</b>														
484+50	13-3	SOUTH MAIN ST					72 x 48	24.0					34	4 x 6 WOOD POSTS (2 POSTS @ 17 FT)
501+50	13-4	WOLF CREEK RD W/ARROW					132 x 54	49.5					40	4 x 6 WOOD POSTS (18 FT AND 22 FT POSTS)
509+50	13-6	EXIT W/ARROW					72 x 60	30.0					30	4 x 6 WOOD POSTS (2 POSTS @ 15 FT)
519+75	13-5	WOLF CREEK RD					150 x 36	37.5					38	4 x 6 WOOD POSTS (2 POSTS @ 19 FT)
521+50	13-5	WOLF CREEK RD					150 x 36	37.5					36	4 x 6 WOOD POSTS (2 POSTS @ 18 FT)
531+75	13-6	EXIT W/ARROW					72 x 60	30.0					30	4 x 6 WOOD POSTS (2 POSTS @ 15 FT)
540+00	13-4	WOLF CREEK RD W/ARROW					132 x 54	49.5					30	4 x 6 WOOD POSTS (2 POSTS @ 15 FT)
551+75	13-7	SOUTH SAMUEL RD					96 x 48	32.0					34	4 x 6 WOOD POSTS (2 POSTS @ 17 FT)
568+50	13-8	NORTH SAMUEL RD					96 x 48	32.0					36	4 x 6 WOOD POSTS (2 POSTS @ 18 FT)
574+00	13-2	WOLF CREEK RD EXIT-1/2MILE					144 x 54	54.0					42	4 x 6 WOOD POSTS (2 POSTS @ 21 FT)
598+00	13-9	WOLF CREEK RD EXIT-1 MILE					144 x 54	54.0					38	4 x 6 WOOD POSTS (2 POSTS @ 19 FT)
<b>WOLF CREEK ROAD RAMP A</b>														
13+00	Z	BUCKLE UP (R5-1100)			48 X 54	18							32	4 x 6 WOOD POSTS (2 POSTS @ 16 FT )
<b>WOLF CREEK ROAD RAMP B</b>														
25+00 LT	X	WRONG WAY	36 X 24	6.00									13	
25+00 RT	X	WRONG WAY	36 X 24	6.00									12	
28+56.56	J	STOP (R1-1)	30 X 30	5.56									32	
28+56.56	L1	STOP AT LINE (R10-1100)	30 X 18	3.75										
28+56.56	W	DO NOT ENTER (R5-1)	30 X 30	6.25										
28+68.47	J	STOP (R1-1)	30 X 30	5.56									32	
28+68.47	L1	STOP AT LINE (R10-1100)	30 X 18	3.75										
28+68.47	W	DO NOT ENTER (R5-1)	30 X 30	6.25										
<b>WOLF CREEK ROAD RAMP C</b>														
10+50	I	YIELD (R1-2)	36 X 36 X 36	4.50						14				
13+00	Z	BUCKLE UP (R5-1100)			48 X 54	18							32	4 x 6 WOOD POSTS (2 @ 16 FT )
<b>WOLF CREEK ROAD RAMP D</b>														
25+00 LT	X	WRONG WAY	36 X 24	6.00									13	
25+00 RT	X	WRONG WAY	36 X 24	6.00									12	
28+60	J	STOP (R1-1)	30 X 30	5.56									16	
28+60	W	DO NOT ENTER (R5-1)	30 X 30	6.25										
28+71	J	STOP (R1-1)	30 X 30	5.56									16	
<b>WOLF CREEK ROAD</b>														
83+65	J	STOP (R1-1)	30 X 30	5.56									16	
89+81	S	BIKE ROUTE (D11-1)	18 X 18	2.25						12				
89+91	I	YIELD (R1-2)	36 X 36 X 36	4.50						10				
91+00	I	YIELD (R1-2)	36 X 36 X 36	4.50						13				
92+00	H	SPEED LIMIT 30 (R2-1)	24 X 30	5.00						13				
94+00	W-2	IL 13 EAST / IL 13 WEST					84 X 78	45.5					42	4 x 6 WOOD POSTS (2 POSTS @ 21 FT)
98+00	W-5	<- IL 13 WEST CARBONDALE					102 X 54	38					36	4 x 6 WOOD POSTS (2 POSTS @ 18 FT)
101+50	W-4	<- IL 13 EAST MARION					90 X 54	33.75					34	4 x 6 WOOD POSTS (2 POSTS @ 17 FT)
105+00	W-3	IL 13 WEST / IL 13 EAST					84 X 78	45.5					38	4 x 6 WOOD POSTS (2 POSTS @ 19 FT)
112+00	H	SPEED LIMIT 30 (R2-1)	24 X 30	5.00						14				
<b>HAWKEYE COURT</b>														
10+30	W-1	WOLF CREEK RD	36 X 8	2.00								14	1	
10+30	N-11	HAWKEYE CT	30 X 8	1.67										
10+50	J	STOP (R1-1)	30 X 30	5.56						25				
10+50	L1	STOP AT LINE (R10-1100)	30 X 18	3.75										
<b>COUNTRY AIRE DRIVE</b>														
9+72	J	STOP (R1-1)	30 X 30	5.56									13	
10+39	J	STOP (R1-1)	30 X 30	5.56									13	
<b>SHEET TOTALS</b>				<b>128</b>		<b>36</b>		<b>590</b>	<b>101</b>	<b>188</b>	<b>14</b>	<b>1</b>	<b>602</b>	