

SEEDING SCHEDULE

LOCATION			SEEDING CLASS 1A	SEEDING CLASS 2	SEEDING CLASS 7	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH METHOD 2	AGRICULTURE GROUND LIMESTONE	REMARKS
STATION	TO	STATION	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND	ACRE	TON	
IL 13												
479+50.00	-	492+29.77		2.94	2.94	147.00	529	529	529	5.88	5.88	
492+29.77	-	561+17.50		22.64	22.64	1,132.00	4,075	4,075	4,075	45.28	45.28	INCLUDES RAMP INFIELD AREAS
561+17.50	-	592+90.74		6.75	6.75	338.00	1,215	1,215	1,215	13.50	13.50	
RAMP A												
10+00.00	-	33+89.90		2.23	2.23	112.00	401	401	401	4.46	4.46	RAMP A, RT
RAMP B												
10+00.00	-	29+21.90		2.21	2.21	111.00	398	398	398	4.42	4.42	RAMP B, RT
RAMP C												
10+00.00	-	28+54.54		3.20	3.20	160.00	576	576	576	6.40	6.40	RAMP C, RT
RAMP D												
10+00.00	-	29+21.40		2.04	2.04	102.00	367	367	367	4.08	4.08	RAMP D, RT
WOLF CREEK ROAD												
83+02.00	-	98+31.08	0.14	1.24	1.38	69.00	248	248	248	2.76	2.76	
101+04.92	-	116+70.88	0.58	2.39	2.97	149.00	534	534	534	5.93	5.93	
HAWKEYE COURT												
10+00.00	-	11+35.00	0.05		0.05	3.00	9	9	9	0.10	0.10	
NORTH FRONTAGE ROAD												
22+55.43	-	28+01.14		1.17	1.17	59.00	211	211	211	2.34	2.34	
50+75.00	-	128+21.17	0.17	9.42	9.59	480.00	1,726	1,726	1,726	19.18	19.18	
COUNTRY AIRE DRIVE												
8+78.46	-	11+80.00	0.04	0.17	0.21	11.00	37	37	37	0.42	0.42	
FLEMING ROAD												
30+00.00	-	33+50.00		0.44	0.44	22.00	79	79	79	0.88	0.88	
DONNA DRIVE												
85+21.41	-	100+00.00		2.49	2.49	125.00	448	448	448	4.98	4.98	
100+00.00	-	144+16.11	0.05	3.81	3.86	193.00	695	695	695	7.72	7.72	
SARA LANE												
8+20.00	-	10+00.00	0.12		0.12	7.00	22	22	22	0.24	0.24	
SARA LANE OUTLET												
5+00.00	-	10+87.07	0.05	0.21	0.26	14.00	47	47	47	0.52	0.52	
MAIN STREET SOUTH												
1+00.00	-	3+55.00		0.20	0.20	10.00	36	36	36	0.40	0.40	
3+55.00	-	7+66.00		0.12	0.12		14	10	10	0.22	0.22	
MAIN STREET NORTH												
0+00.00	-	15+07.50	0.48	0.82	1.30	65.00	234	234	234	2.60	2.60	
SAMUEL ROAD												
6+00.00	-	10+90.00		0.29	0.29	15.00	53	53	53	0.59	0.59	
15+42.43	-	19+70.77		0.32	0.32	16.00	58	58	58	0.64	0.64	
BRIGGS ROAD												
6+26.09	-	9+36.00	0.08	0.12	0.20	10.00	35	35	35	0.39	0.39	
10+24.00	-	13+22.78		0.26	0.26	13.00	47	47	47	0.52	0.52	
BRIGGS ROAD SPUR												
100+00.00	-	102+70.00		0.24	0.24	12.00	42	42	42	0.47	0.47	
PROJECT TOTALS			1.75	65.72	67.47	3,375	12,137	12,133	12,133	134.92	134.92	

- NOTES:**
- FOR ADDITIONAL QUANTITY FOR TEMPORARY EROSION CONTROL SEEDING SEE DRAWING NO. SCH-39.