

# EROSION CONTROL SCHEDULE

LOCATION				EROSION CONTROL BLANKET SO YD	TEMPORARY DITCH CHECKS FOOT	PERIMETER EROSION BARRIER FOOT	TEMPORARY EROSION CONTROL SEEDING POUND	REMARKS
STATION	TO	STATION						
<b>IL 13 WESTBOUND</b>								
480+00	-	488+05	LT	1,067	178		1,658	
488+06	-	490+00	LT	201	60			
493+28	-	497+00	LT			379		
497+00	-	502+75	LT	775	152			
502+80	-	504+95	LT	220	90			
505+00	-	507+00	LT	215	110			
507+05	-	509+93	LT	405	38			
530+53	-	535+65	LT	702	72			
535+75	-	537+20	LT	215	84			
537+30	-	543+30	LT	980	120			
543+36	-	546+99	LT	553	84			
547+33	-	557+90	LT	1,617	222			
558+00	-	560+00	LT	296	24			
561+00	-	569+69	LT	1,291	236			
569+78	-	572+50	LT	419	112			
573+60	-	577+60	LT	514	186			
578+75	-	584+05	LT	826	140			
584+20	-	585+90	LT	260	28			
587+12	-	590+35	LT	495	42			
590+50	-	592+50	LT	312	56			
<b>IL 13 EASTBOUND</b>								
479+50	-	486+60	RT	1,101	140		1,007	
487+00	-	492+00	RT			505		
493+57	-	504+50	RT			1,100		
538+55	-	540+00	RT			150		
541+50	-	543+30	RT	288	60			
543+42	-	546+90	RT	531	105			
547+07	-	557+47	RT	1,708	255			
557+63	-	558+70	RT	179	30			
558+70	-	559+50	RT			100		
560+95	-	568+00	RT	991	152			
568+50	-	574+90	RT			645		
575+20	-	577+83	RT			265		
579+00	-	581+50	RT	392	56			
581+50	-	584+10	RT			265		
584+25	-	585+96	RT			200		
587+00	-	588+00	RT			100		
<b>RAMP A</b>								
11+00	-	13+00	LT/RT	1,661				AS DIRECTED BY ENGINEER
10+94	-	19+45	RT	946	230		134	
19+54	-	21+00	RT	160	10			
10+62	-	19+50	LT	14,407	156			
<b>RAMP B</b>								
23+00	-	28+00	LT/RT	5,687				AS DIRECTED BY ENGINEER
18+90	-	28+50	LT	14,003	130	890	207	
19+00	-	25+30	RT	1,453	344			
25+45	-	28+35	RT	494	186			
<b>RAMP C</b>								
11+00	-	18+00	LT/RT	3,978				AS DIRECTED BY ENGINEER
10+70	-	19+80	LT	14,246	315	535	192	
10+60	-	28+54	RT	14,201	404			
<b>RAMP D</b>								
21+00	-	28+00	LT/RT	3,791				AS DIRECTED BY ENGINEER
18+00	-	27+97	LT	14,006	50		232	
10+00	-	28+85	RT	8,568	130			
<b>SHEET TOTALS</b>				<b>114,152</b>	<b>4,787</b>	<b>5,134</b>	<b>3,430</b>	

FILE NAME =	USER NAME = \$USER\$	DESIGNED - KN	REVISED -
et:\pw\work\p\dot\lavenderba\0363618\0978221-sht-SCH-37.dgn		DRAWN - AS	REVISED -
	PLOT SCALE = 2.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/31/2014	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL SCHEDULE**

SCALE: SHEET NO. 37 OF 56 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-3)R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	79
DRAWING NO. <b>SCH-37</b>			CONTRACT NO. 78221	
ILLINOIS FED. AID PROJECT				