

ROADWAY REMOVAL SCHEDULE

LOCATION			PAVEMENT REMOVAL	PAVEMENT MARKING REMOVAL	PAVED SHOULDER REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB & GUTTER REMOVAL	GUTTER REMOVAL	SIDEWALK REMOVAL	PAVED DITCH REMOVAL	REMOVE EXISTING CONCRETE FOUNDATION	ISLAND REMOVAL	CONCRETE RETAINING WALL REMOVAL	FENCE REMOVAL	REMARKS
STATION	TO	STATION	SO YD	SO FT	SO YD	SO YD	FOOT	FOOT	SO FT	FOOT	EACH	SOFT	FOOT	FOOT	
DONNA DRIVE															
85+21.41	-	90+19.08	1,522												
90+90.20	-	107+97.02	861												
101+50.95	-	101+51.75												125	
102+83.12	-	103+65.15												148	
103+77.11	-	104+24.52												54	
104+51.56	-	105+45.63												86	
105+40.63	-	105+78.42												136	
105+66.19	-	106+31.85												138	
107+83.87	-	115+60.00												1,113	
107+84.87	-	115+45.81	2,464												
107+87.85	-	108+84.05												159	
115+45.81	-	121+67.42	1,205												
121+67.42	-	123+73.14	377			54									
125+75.50	-	131+39.97												570	
126+96.09	-	127+02.80												16	
129+69.38	-	132+78.62	533												
SARA LANE															
8+20.00	-	9+90.46	353			30									
SARA LANE OUTLET															
6+48.34	-	8+94.60												253	
MAIN STREET SOUTH															
1+43.08	-	3+55.00	632		160										
3+55.00	-	5+85.00	595					60							
MAIN STREET NORTH															
0+00.00	-	15+07.50	4,119		624										
0+07.12	-	1+18.94					171								
0+65.22	-	0+75.76										223			TO BE REPLACED WITH TEMPORARY PAVEMENT FOR CONSTRUCTION PRE-PHASE
7+45.20	-	9+33.82				54									
6+47.92	-	14+85.21							3000						
7+41.75	-	12+80.10													
SHEET TOTALS			12,661	0	784	138	171	60	3,000	0	0	223	0	2,798	

NOTES:

- FOR TEMPORARY PAVEMENT QUANTITY,
SEE DRAWING NO. SCH-01.