ROADWAY REMOVAL SCHEDULE

					PAVEMENT	PAVED	DRIVEWAY	COMBINATION CURB &				REMOVE EXISTING		CONCRETE RETAINING		
LOCATION				MARKING		PAVEMENT	GUTTER	GUTTER		PAVED DITCH	I I	ISL AND	WALL	FENCE		
				REMOVAL	REMOVAL	REMOVAL	REMOVAL	REMOVAL	REMOVAL	REMOVAL	REMOVAL	FOUNDATION	REMOVAL	REMOVAL	REMOVAL	REMARKS
	STATION	TO	STATION	SO YD	SO FT	SO YD	SO YD	FOOT	FOOT	SO FT	FOOT	EACH	SOFT	FOOT	FOOT	
PLAZA DR	IVF FAST															
LALA DI	126+47.01	Τ-Ι	127+73.05	356		149										
	126747.01		121713.03	330		113										
SAMUEL R	OAD															
	6+00.00	-	10+90.00	1,108												
	15+42.43	-	17+12.25	805		171										
	18+00.94	-	19+70.77	540		151										
BRIGGS R	DAD															
	6+37.49	-	9+23.49	924		149										
	10+12.17	-	12+95.40	806		163										
BRIGGS S	PUR ROAD															
	100+62.89	-	102+70.00	391												
		S	SHEET TOTALS	4,930	0	783	0	0	0	0	0	0	0	0	0	
SHEET TOTALS FROM REMOVAL SCH-43		22,842	3,389	50,900	638	0	0	0	810	1	36	55	1,966			
			MOVAL SCH-44		0	784	138	171	60	3,000	0	0	223	0	2,798	
	PROJECT TOTALS 40,433			3,389	52,467	776	171	60	3,000	810	1	259	55	4,764		

BUILDING REMOVAL SCHEDULE

	L	OCATIO	ON		BUILDING REMOVAL NO. 2	BUILDING REMOVAL NO. 3	REMARKS
	STATION	TO	STATION	LT/RT	L SUM	L SUM	
NORT	H FRONTAGE	ROAD					
	66+46.16		66+68.68	LT	1		
	67+66.44		68+27.13	RT		1	
		PRO	JECT TOTALS	<u> </u>	1	1	

FILE NAME =	USER NAME = \$USER\$	DESIGNED - KN	REVISED -	Γ
c:\pw_work\pwidot\lavenderba\d0363618\D	178221-sht-SCH-45.dgn	DRAWN - AS	REVISED -	
	PLOT SCALE = 2.0000 '/ in.	CHECKED -	REVISED -	
	PLOT DATE = 1/31/2014	DATE -	REVISED -	

ROADWAY REMOVAL SCHEDULE						5	SECTION			TOTAL SHEETS	SHEE NO.
	BUILDING REMO		331	(1-3)R-2, N	N-4, TS-4,	HBK-1	WILLIAMSON	733	87		
							SCH-4	15	CONTRAC	NO.	78221
	SHEET NO. 45 OF 56 SHEE	TS STA.	١.	TO STA.			ILLINOIS	FED. Al	D PROJECT		