

ROUTE NO.	SECTION	CITY	TOTAL SHEETS	SHEET NO.
F.A.U. 9719	06-00054 -00-FP	HERRIN	733	714
ILLINOIS		RUSHING DR. CONNECTOR		

CONTRACT NO. 99468

NOTES:

ALL STATIONING IS APPROXIMATE. EXACT STATIONING TO BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE QUANTITIES SHOWN IN THE SCHEDULES ARE ESTIMATES ONLY. THE ACTUAL AMOUNTS OF THE VARIOUS ITEMS AND THEIR LOCATIONS SHALL BE DETERMINED BY THE ENGINEER.


THE OFFSETS FOR THE STORM SEWER STRUCTURES ARE TO THE CENTER OF STRUCTURE. PLEASE NOTE THESE STATION AND OFFSET VALUES ARE APPROXIMATE ONLY AND THE FINAL LOCATION SHALL BE DETERMINED IN THE FIELD.

STORM SEWER STRUCTURE SCHEDULE							
INLET NO.	STATION	OFFSET	T.C. ELEV	N INVERT	S INVERT	E INVERT	W INVERT
1	3+00	16.75 LT	455.74	451.79	451.79	451.79	
1A	3+00	16.75 RT	455.74				451.87
2	5+50	16.75 LT	460.10	454.92	454.92	454.92	
2A	5+50	16.75 RT	460.10				455.00
3	8+00	16.75 LT	463.60	457.42	457.42	457.42	
3A	8+00	16.75 RT	463.60				457.50
4	11+05.67	16.75 LT	463.62		460.62	460.62	
4A	11+05.67	16.75 RT	463.62				460.70
5	16+20	16.75 RT	464.00	458.01			458.01
5A	16+20	16.75 LT	464.00			458.35	
7	18+00	16.75 RT	462.00	456.20	456.20		456.20
7A	18+00	16.75 LT	462.00			456.38	
8	20+00	16.75 RT	459.60	454.16	454.16		454.16
8A	20+00	16.75 LT	459.60			454.24	
10	22+27.17	16.75 RT	456.92	451.85	451.85		451.85
10A	22+27.17	16.75 LT	456.92			451.93	
11	24+50	16.75 RT	456.92	449.58	449.58		449.58
11A	24+50	16.75 LT	456.92			449.75	
12	26+50	16.75 RT	451.95	447.55	447.55		447.55
12A	26+50	16.75 LT	451.95			447.72	
13	28+50	16.75 RT	449.59	444.67	444.67		444.67
13A	28+50	16.75 LT	449.59			444.84	

PAVEMENT MARKING SCHEDULE				
LOCATION	4" WHITE (FEET)	4" YELLOW SOLID (FEET)	4" YELLOW DASHED (CENTERLINE) (FEET)	24" STOP BAR (FEET)
2+46 TO 6+00	710		90	
6+00 TO 12+00	1200		150	
12+00 TO 18+00	1200		150	
18+00 TO 24+00	1200		150	
24+00 TO 28+60	920		115	
30+00 TO 30+50	5230		655	

TREE REMOVAL ACRES	
STATION TO STATION	ACRES
2+46 TO 8+81	0.05
8+81 TO 15+16	0.11
15+16 TO 21+51	0.00
21+51 TO 27+86	0.02
27+86 TO 28+60	0.01

TREE REMOVALS			
STATION	OFFSET	OVER 15"	6" TO 15"
3+92	25' RT	24"	
4+12	17' RT	24"	
4+49	19' RT	24"	
4+58	17' RT		15"
TOTALS		72 UNITS	15 UNITS

STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM LICENSE NO. 184-004515		© 2007 ALL RIGHTS RESERVED	
REVISIONS		 CLARIDA² & ZIEGLER ENGINEERING CO. 410 North Court St, P.O. Box 937 Marion, Illinois 62959 Phone - (618)993-6411, Fax - (618)993-6750	
DATE	NO.		
SUMMARY OF QUANTITIES AND SCHEDULES RITTER ROAD HERRIN, ILLINOIS			
Date	NOV 2012	DR. By	T.W.
Scale	NONE	Job No.	11120
Sheet No.	714	of	733