

COUNTY:	WILLIAMSON		
LOCATION:			
ROUTE:	F.A.P. 331 (IL 13)		
FUNDING:	80% FEDERAL 20% STATE		
WORK TYPE:	ROADWAY	BRIDGE	SAFETY
CONSTRUCTION TYPE CODE	0001	0008	0021
UNIT	TOTAL QUANTITY		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	SAFETY
28000305	TEMPORARY DITCH CHECKS	FOOT	11335	11335		
28000400	PERIMETER EROSION BARRIER	FOOT	12763	12763		
28000500	INLET AND PIPE PROTECTION	EACH	191	191		
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	3711	3711		
28200200	FILTER FABRIC	SQ YD	10	10		
28300400	AGGREGATE DITCH	TON	7	7		
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	110662	110662		
30201500	LIME	TON	2814	2814		
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	10121	10121		
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	83248	83248		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	7962	7962		
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	895	895		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	54897	54897		
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	2063	2063		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	200	200		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	5000	5000		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	45594	45594		
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	7000	7000		

FILE NAME =	USER NAME = #USER#	DESIGNED - KN	REVISED -
c:\pwwork\p\ridot\levanderba\036261810	78221-hst-500-02.dgn	DRAWN - AS	REVISED -
	PLOT SCALE = 2.0000 1/1 in.	CHECKED -	REVISED -
	PLOT DATE = 1/31/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 2 OF 16 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	11-31R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	8
DRAWING NO. S00-02		CONTRACT NO. 78221		
[ILLINOIS] FED. AID PROJECT				