

CODE NO.	ITEM DESCRIPTION	COUNTY:		WILLIAMSON		
		LOCATION:	ROUTE:	F.A.P. 331 (IL 13)		
		FUNDING:		90% FEDERAL 10% STATE		
		WORK TYPE:		ROADWAY	BRIDGE	SAFETY
		CONSTRUCTION TYPE CODE:		0001	0008	0021
		UNIT	TOTAL QUANTITY			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	6090		6090	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	292080		292080	
50800530	MECHANICAL SPLICERS	EACH	40		40	
50901750	PARAPET RAILING	FOOT	423		423	
51100100	SLOPE WALL 4 INCH	SO YD	797		797	
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1744		1744	
51202305	DRIVING PILES	FOOT	1744		1744	
51203900	TEST PILE STEEL HP14X89	EACH	1		1	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	40		40	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	20		20	
54001001	BOX CULVERT END SECTIONS CULVERT NO. 1	EACH	1	1		
54001002	BOX CULVERT END SECTIONS CULVERT NO. 2	EACH	1	1		
54010404	PRECAST CONCRETE BOX CULVERTS 4' x 4'	FOOT	27	27		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	27	27		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	9	9		
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	65	65		
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	803	803		

FILE NAME =	USER NAME = *USER*	DESIGNED - KN	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\levanderba\d8263618\078221-sht-500-PS.dgn	78221-sht-500-PS.dgn	DRAWN - AS	REVISED -					331	11-31R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	11
PLOT SCALE = 2.0000 1/16"	CHECKED -	REVISED -	REVISED -		DRAWING NO. <b>S00-05</b>	CONTRACT NO. 78221						
PLOT DATE = 1/31/2014	DATE -	REVISED -	REVISED -		SCALE:	SHEET NO. 5 OF 16 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			