

COUNTY:	WILLIAMSON		
LOCATION:			
ROUTE:	F.A.P. 331 (IL 13)		
FUNDING:	90% FEDERAL 10% STATE		
WORK TYPE:	ROADWAY	BRIDGE	SAFETY
CONSTRUCTION TYPE CODE:	0001	0008	0021
UNIT	TOTAL QUANTITY		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	SAFETY
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	146	146		
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	156	156		
542A0247	PIPE CULVERTS, CLASS A, TYPE 1 42"	FOOT	76	76		
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	67	67		
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	251	251		
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	189	189		
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	137	137		
542A1909	PIPE CULVERTS, CLASS A, TYPE 3 24"	FOOT	180	180		
542A2779	PIPE CULVERTS, CLASS A, TYPE 4 54"	FOOT	169	169		
542A3391	PIPE CULVERTS, CLASS A, TYPE 5 36"	FOOT	96	96		
542A3397	PIPE CULVERTS, CLASS A, TYPE 5 42"	FOOT	198	198		
542A4021	PIPE CULVERTS, CLASS A, TYPE 6 36"	FOOT	260	260		
542A4039	PIPE CULVERTS, CLASS A, TYPE 6 54"	FOOT	315	315		
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	116	116		
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	147	147		
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	61	61		
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	110	110		

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
c:\pwwork\pwwork\lavenderba\d0203018\78221-ht-900-26.dgn	USER	KN	-
		DRAWN :	REVISED :
		AS	-
		CHECKED :	REVISED :
			-
		DATE :	REVISED :
			-

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 6 OF 16 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1-3)R-2, H-4, TS-4, HBK-1	WILLIAMSON	733	12
DRAWING NO.	SOQ-06	CONTRACT NO.	78221	
ILLINOIS FED. AID PROJECT				