

COUNTY:	WILLIAMSON		
LOCATION:			
ROUTE:	F.A.P. 331 (IL 13)		
FUNDING:	90% FEDERAL 10% STATE		
WORK TYPE:	ROADWAY	BRIDGE	SAFETY
CONSTRUCTION TYPE CODE	0001	0008	0021
UNIT	TOTAL QUANTITY		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0001	BRIDGE 0008	SAFETY 0021
55100900	STORM SEWER REMOVAL 18"	FOOT	50	50		
55101200	STORM SEWER REMOVAL 24"	FOOT	57	57		
55101400	STORM SEWER REMOVAL 30"	FOOT	771	771		
55101600	STORM SEWER REMOVAL 36"	FOOT	40	40		
55101800	STORM SEWER REMOVAL 42"	FOOT	202	202		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	187		187	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	24	24		
60100945	PIPE DRAINS 12"	FOOT	200	200		
60107600	PIPE UNDERDRAINS 4"	FOOT	24303	24303		
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	564	564		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6		
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224459	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60224469	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		