

CODE NO.	ITEM DESCRIPTION	COUNTY: WILLIAMSON		
		CONSTRUCTION	BRIDGE	SAFETY
		F.A.P. 331 (IL 13)		
		80% FEDERAL 20% STATE		
		ROADWAY	BRIDGE	SAFETY
		0001	0008	0021
UNIT	TOTAL QUANTITY			
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	16	16
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3389	3389
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	759	759
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
* 81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	205	205
* 81028770	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3" DIA.	FOOT	250	250
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	250	250
* 81300555	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 8"	EACH	3	3
* 81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2760	2760
* 81603040	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3400	3400
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	260	260
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	780	780
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO 4	FOOT	520	520
* 82103900	LUMINARE, SODIUM VAPOR, MULTI-MOUNT 250 WATT	EACH	20	20
* 82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240 VOLT, 60 AMP	EACH	1	1
* 83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H., TENON MOUNT	EACH	16	16

FILE NAME =
 USER NAME = *USER*
 78221-INT-500-14.dgn
 C:\pwwork\pwwork\lavenderba\0363618\0

DESIGNED - KN
 DRAWN - AS
 CHECKED -
 DATE -
 PLOT SCALE = 2.0000" / 1" =
 PLOT DATE = 1/21/2014

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	TOTAL SHEETS	TO STA.
	14 OF 16		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	11-3R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	20
DRAWING NO. 500-14			CONTRACT NO. 78221	
ILLINOIS FED. AID PROJECT				

* SPECIALTY ITEM