

COUNTY:	WILLIAMSON		
LOCATION:			
ROUTE:	F.A.P. 331 (IL 13)		
FUNDING:	90% FEDERAL 10% STATE		
WORK TYPE:	ROADWAY	BRIDGE	SAFETY
CONSTRUCTION TYPE CODE	0001	0008	0021
UNIT	TOTAL QUANTITY		

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0001	BRIDGE 0008	SAFETY 0021
* 83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M.H. TENON MOUNT-TWIN	EACH	2			2
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	16			16
* 83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	2			2
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	56			56
* 88600100	DETECTOR LOOP, TYPE 1	FOOT	2152	2152		
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1		
X4200400	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB	SQ YD	9050	9050		
* A2C025G3	TREE, CERCIS CANADENSIS (REDBUD), CONTAINER GROWN, 3-GALLON	EACH	32	32		
* C2C01936	SHRUB, CORNUS SERICEA BAILEYI (BAILEY REDOSIER DOGWOOD), 3' CONTAINER	EACH	21	21		
* D2002736	EVERGREEN, PINUS NIGRA (AUSTRIAN PINE), 3' HEIGHT, BALLED AND BURLAPPED	EACH	16	16		
X0323444	DECORATIVE STEEL RAILING	FOOT	211		211	
X2020502	BRACED EXCAVATION	CU YD	188		188	
<input type="checkbox"/> X2503100	MOWING	UNIT	433	433		
X3112900	SUBBASE GRANULAR MATERIAL (SPECIAL)	CU YD	250	250		
X4402805	ISLAND REMOVAL	SQ FT	259	259		
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	335		335	
X6024240	INLETS, SPECIAL	EACH	71	71		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
X7011830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	EACH	14	14		
X7011832	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	EACH	1	1		
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	5883	5883		

FILE NAME =	USER NAME = *USER*	DESIGNED - KN	REVISED -
c:\pwwork\p1\dot\lavenderba\836361810	78221-int-500-15.dgn	DRAWN - AS	REVISED -
	PLOT SCALE = 2.0000" / 1"	CHECKED -	REVISED -
	PLOT DATE = 1/31/2014	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 15 OF 16 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	11-31R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	21
DRAWING NO. S00-15		CONTRACT NO. 78221		
ILLINOIS FED. AID PROJECT				

\* SPECIALTY ITEM     Non-Participating (100% State)