

COUNTY:		WILLIAMSON		
LOCATION:		F.A.P. 331 (IL 13)		
ROUTE:		90% FEDERAL 10% STATE		
FUNDING:				
WORK TYPE:		ROADWAY	BRIDGE	SAFETY
CONSTRUCTION TYPE CODE:		0001	0008	0021
UNIT	TOTAL QUANTITY			

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	SAFETY
* X8110522	CONDUIT ATTACHED TO STRUCTURE, 2" DIA. STAINLESS STEEL	FOOT	30			30
Z0004002	BOLLARDS	EACH	34			34
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1		
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0022800	FENCE REMOVAL	FOOT	4764	4764		
Z0034105	MATERIAL TRANSFER DEVICE	TON	18713	18713		
Z0041500	PLUG EXISTING CULVERTS	EACH	1	1		
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	10997	10997		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	234		234	
Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L SUM	1	1		
* Z0054500	ROCK FILL	TON	200	200		
Z0062456	TEMPORARY PAVEMENT	SQ YD	1010	1010		
∅ Z0076600	TRAINEES	HOURL	2500	2500		
Z0065100	SETTLEMENT PLATFORMS	EACH	4	4		
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	2500	2500		
Z0075496	CONCRETE RETAINING WALL REMOVAL	FOOT	55	55		
X5030290	STAINING CONCRETE STRUCTURES	SQ FT	5751		5751	
X0327731	PARAPET MOUNTED BRIDGE LIGHTING SYSTEM	L SUM	1		1	
X0327732	PRECAST ORNAMENTAL CENTER PILASTER	EACH	2		2	
X0327733	PRECAST ORNAMENTAL CORNER PILASTER	EACH	4		4	

FILE NAME =	USER NAME = USER*	DESIGNED - KN	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
g:\p\work\p\p\dat\lavanderba\0363610\078221\ent-500-16.dgn		DRAWN - AS	REVISED -					331	11-31R-2, N-4, TS-4, HBK-1	WILLIAMSON	733	22
PLOT SCALE = 2.0000" / 1"		CHECKED -	REVISED -		DRAWING NO. <b>500-16</b>	CONTRACT NO. 78221						
PLOT DATE = 1/31/2014		DATE -	REVISED -		SCALE:	SHEET NO. 16 OF 16 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			

\* SPECIALTY ITEM ∅ 0042