

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0011
				ROADWAY	S.N. 035-0017
20200100	EARTH EXCAVATION	CU YD	81	81	
20300100	CHANNEL EXCAVATION	CU YD	2100	2100	
25000210	SEEDING, CLASS 2A	ACRE	0.27	0.27	
25000350	SEEDING, CLASS 7	ACRE	0.27	0.27	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25	25	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	25	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	25	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6	0.6	
25100115	MULCH, METHOD 2	ACRE	0.27	0.27	
25100630	EROSION CONTROL BLANKET	SQ YD	1320	1320	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	110	110	
28000400	PERIMETER EROSION BARRIER	FOOT	813	813	
28100109	STONE RIPRAP, CLASS A5	SQ YD	1534		1534
28200200	FILTER FABRIC	SQ YD	1534		1534

141 * SPECIALTY ITEM



USER NAME - * keh	DESIGNED - NHP	REVISED -
ESCA PROJECT NO. 1835.03	DRAWN - JLF	REVISED -
PLOT SCALE - 0.1687" / IN.	CHECKED - JMS	REVISED -
PLOT DATE - 1/22/2014 5:06:14 PM	DATE - 12/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET NO. 1 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	1158-1	HARDIN	70	3
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		CONTRACT NO. 78263		