

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0011
				ROADWAY	S. N. 035-0017
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1		1
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	314.1		314.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	289.6		289.6
50300260	BRIDGE DECK GROOVING	SQ YD	632		632
50300265	SEAL COAT CONCRETE	CU YD	146.4		146.4
50300300	PROTECTIVE COAT	SQ YD	858	46	812
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3258		3258
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	95500		95500
50800515	BAR SPLICERS	EACH	718		718
51201800	FURNISHING STEEL PILES HP14X73	FOOT	1466		1466
51202305	DRIVING PILES	FOOT	396		396
51203800	TEST PILE STEEL HP14X73	EACH	2		2

14 \* SPECIALTY ITEM



USER NAME = kah  
 ESCA PROJECT NO. 1835.03  
 PLOT SCALE = 0.1667 "/>

DESIGNED - NHP  
 DRAWN - JLF  
 CHECKED - JMS  
 DATE - 12/13

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
782	118B-1	HARDIN	70	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 78263	