

**EARTHWORK**

STATION / LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	STRUCTURE EXCAVATION	STRUCTURE EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	CHANNEL EXCAVATION
	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
U.S. ROUTE 45							
828+00.00 - 830+00.00							750
O.R. 163							
50+14.86 - 50+69.31	32	24	65	95	71	30	
51+14.31 - 52+40.00	51	38	137	90	68	-31	
<b>TOTALS</b>	<b>83</b>	<b>62</b>	<b>202</b>	<b>185</b>	<b>139</b>	<b>-1</b>	<b>750</b>

NOTE: REMAINDER OF EARTHWORK BALANCE CAN BE FILLED WITH CHANNEL EXCAVATION.

FILE NAME = L:\IDOT\0806610\W0.12\Draw\Sheets\0978267-sh-t-schedule.dgn	USER NAME = Rob Heady	DESIGNED - BMB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES O.R. 163 OFF U.S. ROUTE 45 (F.A.P. 881)</b>	O.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
Default	PLOT SCALE = 100.0000' / 1in.	DRAWN - BMB	REVISED -			163	34B-2	JOHNSON	37	7	
	PLOT DATE = 11/26/2013	CHECKED - JMM	REVISED -			<b>CONTRACT NO. 78267</b>					
		DATE - DECEMBER 2013	REVISED -			SCALE:	SHEET OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		