

SUMMARY OF QUANTITIES		FUNDING - STP 80% FEDERAL, 20% STATE	
		CONSTRUCTION CODE - 0011	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	0.25
20200100	EARTH EXCAVATION	CU YD	83
20300100	CHANNEL EXCAVATION	CU YD	750
25000200	SEEDING, CLASS 2	ACRE	0.50
25000350	SEEDING, CLASS 7	ACRE	0.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1
25100115	MULCH, METHOD 2	ACRE	0.50
25100630	EROSION CONTROL BLANKET	SO YD	770
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100
28000305	TEMPORARY DITCH CHECKS	FOOT	40
28000500	INLET AND PIPE PROTECTION	EACH	1

SUMMARY OF QUANTITIES		FUNDING - STP 80% FEDERAL, 20% STATE	
		CONSTRUCTION CODE - 0011	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
28100107	STONE RIPRAP, CLASS A4	SO YD	379
28200200	FILTER FABRIC	SO YD	379
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	256
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	12
44004000	PAVED DITCH REMOVAL	FOOT	25
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	185
50300225	CONCRETE STRUCTURES	CU YD	68.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	7.0
50300280	CONCRETE ENCASEMENT	CU YD	4.2
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SO FT	777
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,990
50900305	STEEL RAILING, TYPE T1	FOOT	96
51201610	FURNISHING STEEL PILES HP12X63	FOOT	277