

SUMMARY OF QUANTITIES			
CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE 0040
			083-2022 FUNDING STP 80% FEDERAL 20% STATE
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	52
28000400	PERIMETER EROSION BARRIER	FOOT	578
28100109	STONE RIPRAP, CLASS A5	SQ YD	307
28200200	FILTER FABRIC	SQ YD	307
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	173
42001300	PROTECTIVE COAT	SQ YD	184
44000100	PAVEMENT REMOVAL	SQ YD	125
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	334
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	350
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	31470
50900200	STEEL RAILING, TYPE 2399	FOOT	46
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	135.7

14 ^SEE SPECIAL PROVISIONS

FILE NAME = 0978268-shr-500.dgn	USER NAME = *USER*	DESIGNED - L.F.S.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES OLD IL 13	F.A.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
HAMPTON, LENZHI AND RENWICK, INC. 2045 SPRINGFIELD ROAD, SUITE 201 SPRINGFIELD, ILLINOIS 62761	PLOT SCALE = #SCALE#	DRAWN - T.W.K.	REVISED -			899	9B-1	SALINE	33	4
ILLINOIS PROFESSIONAL DESIGN FIRM 13 1/2 E. 34th COURT, SPRINGFIELD, ILLINOIS 62761	PLOT DATE = 1/23/2014	CHECKED - J.W.F.	REVISED -			CONTRACT NO. 78268		ILLINOIS FED. AID PROJECT		
DATE - 01/14/14				SCALE:	SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.			