

STAGE 1 SHOULDER SCHEDULE

LOCATION STATION TO STATION			COMMENTS	PAVED SHOULDER WIDTH	SHOULDER DEPTH	PCC SHOULDER 12"	HMA SHOULDERS	AGG. SHLDRS, TY. A 8"	SHLDR RUMBLE STRIP	BIT MATLS (PRIME COAT)
				FT	INCH	SQ YD	TON	SQ YD	FOOT	POUNDS
STAGE 1										
840+46.25	TO	847+03.12	NB (I5764B)	8*	12	X	587	X	X	X
847+03.12	TO	866+86.03	NB (I5764B)	8	12	X	1258	X	X	X
866+86.03	TO	869+25.45	NB (I5764B)	8*	12	X	171	X	X	X
875+00.00	TO	879+99.30	NB (I5764B)	8	12	X	317	X	X	X
879+99.30	TO	880+94.86	NB (I5764B)	8	12	X	61	X	X	X
882+15.39	TO	885+00.00	NB (I5764A)	8	12	X	181	X	X	X
830+10.00	TO	844+71.86	NB TO WB (TAPERD1)	8	12	X	928	X	X	X
2388+22.69	TO	2403+05.51	NB TO WB (I5764D)	8	12	X	941	X	X	X
2364+05.07	TO	2386+02.56	NB TO WB (I5764D)	8	12	X	1395	X	X	X
2356+80.00	TO	2363+46.36	WB (I64)	8	12	X	423	X	X	X
830+00.00	TO	885+00.00	SB (I5764A)	8	12	X	3491	X	X	X
2356+80.00	TO	2363+46.36	EB (I64)	8	12	X	423	X	X	X
2364+05.07	TO	2364+52.20	EB TO NB (TAPER1)	8	12	X	30	X	X	X
2364+52.20	TO	2375+00.00	EB TO NB (TAPER1)	8	13	X	724	X	X	X
2371+96.95	TO	2378+41.13	EB TO SB (I5764C)	8*	12	X	369	X	X	X
2378+41.13	TO	2395+58.10	EB TO SB (I5764C)	8	12	X	1090	X	X	X
2395+58.10	TO	2398+72.60	EB TO SB (I5764C)	8*	12	X	268	X	X	X
839+34.91	TO	843+66.07	EB TO SB (TAPERC1)	8*	12	X	129	X	X	X
*SHOULDER WIDTH VARIES				TOTAL STAGE 1			0	12785	0	0

△ REV. 4-10-14

FILE NAME =	USER NAME = rollovr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGE 1 SHOULDER SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\puidot\rollovr\8278568\78276	shlb-top_aoh.tias.dgn	DRAWN -	REVISED -						**	.	JEFFERSON	235	28
#MODELNAME#	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 78276	
	PLOT DATE = 4/4/2014	DATE -	REVISED -										(ILLINOIS) FED. AID PROJECT