

STAGE 5 PAVEMENT SCHEDULE

LOCATION STATION TO STATION			COMMENTS	LANE WIDTH	CRC PAVEMENT 12"	PROC MOD SOIL 12"	LIME	PAVEMENT REINF	STAB SUBBASE 4"	POLY HMA SURF CSE, MIX E	POLY HMA BINDER COURSE	HMA BINDER COURSE	BIT MATLS (PRIME COAT)	POLY BIT MATLS (PC)	RUBBLIZE PCC PVMT	BRIDGE APPR PVT CONN-PCC
				FT	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	TON	TON	POUNDS	POUNDS	SQ YD	SQ YD
STAGE 5																
817+80.00	TO	827+38.12	NB I-57 (I5764B) DL & OS	12	1277	2715	81	1277	2715	X	X	X	X	X	X	X
827+38.12	TO	828+38.12	NB I-57 (I5764B) DL & OS	12	X	283	8	133	283	X	X	X	X	X	X	133
830+20.14	TO	831+20.14	NB I-57 (I5764B) DL & OS	12	X	283	8	133	283	X	X	X	X	X	X	133
831+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	12	922	1959	58	922	1959	X	X	X	X	X	X	X
828+17.13	TO	828+37.13	SB I-57 (I5764A) DL & OS	12	X	57	2	27	57	X	X	X	X	X	X	27
830+18.63	TO	831+18.63	SB I-57 (I5764A) DL & OS	12	X	283	8	133	283	X	X	X	X	X	X	133
831+18.63	TO	836+25.03	SB I-57 (I5764A) DL & OS	12	675	1435	43	675	1435	X	X	X	X	X	X	X
TOTAL STAGE 5					2,874	7,015	208	3,301	7,015	0	0	0	0	0	0	427

STAGE 5 SHOULDER SCHEDULE

LOCATION STATION TO STATION			COMMENTS	PAVED SHOULDER WIDTH	SHOULDER DEPTH	PCC SHOULDER 12"	HMA SHOULDERS	AGG. SHLDRS, TY. A 8"	SHLDR RUMBLE STRIP	BIT MATLS (PRIME COAT)
				FT	INCH	SQ YD	TON	SQ YD	FOOT	POUNDS
STAGE 5										
817+80.00	TO	828+38.12	NB I-57 (I5764B) DL & OS	12	12	1411	X	X	1058	X
830+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	12	12	1055	X	X	791	X
828+17.13	TO	828+37.13	SB I-57 (I5764A) DL & OS	12	12	27	X	X	20	X
830+18.63	TO	836+25.03	SB I-57 (I5764A) DL & OS	12	12	809	X	X	606	X
TOTAL STAGE 5						3,301	0	0	2,476	0

STAGE 5 REMOVAL SCHEDULE

LOCATION STATION TO STATION			COMMENTS	LANE WIDTH	PAVED SHOULDER WIDTH	HMA SURFACE REM, 3 3/4"	HMA SURF REM- BUTT JOINT	PVMT REM	PAVED SHLDR REM	HMA SURFACE REM, 2"
				FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
STAGE 5										
817+80.00	TO	828+38.12	NB I-57 (I5764B) DL & OS	12	12	X	X	1411	1411	X
830+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	12	12	X	X	1055	1055	X
828+17.13	TO	828+37.13	SB I-57 (I5764A) DL & OS	12	12	X	X	27	27	X
830+18.63	TO	836+25.03	SB I-57 (I5764A) DL & OS	12	12	X	X	809	809	X
TOTAL STAGE 5						0	0	3,301	3,301	0

△ REV. 4-10-14