

STAGE 7 PAVEMENT SCHEDULE

LOCATION STATION TO STATION			COMMENTS	LANE WIDTH	CRC PAVEMENT 12"	PROC MOD SOIL 12"	LIME	PAVEMENT REINF	STAB SUBBASE 4"	POLY HMA SURF CSE, MIX E	POLY HMA BINDER COURSE	HMA BINDER COURSE	BIT MATLS (PRIME COAT)	POLY BIT MATLS (PC)	RUBBLIZE PCC PVMT	BRIDGE APPR PVT CONN-PCC
				FT	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	TON	TON	GAL	GAL	SQ YD	SQ YD
STAGE 7																
817+80.00	TO	828+38.12	NB I-57 (I5764B) IL & IS	12	1411	2763	82	1411	2763	X	X	X	X	X	X	244
830+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	12	1055	2066	61	1055	2066	X	X	X	X	X	X	244
STAGE 7																
828+17.13	TO	828+37.13	SB I-57 (I5764A) IL & IS	12	27	52	2	27	52	X	X	X	X	X	X	49
830+18.63	TO	836+25.03	SB I-57 (I5764A) IL & IS	12	809	1583	47	809	1583	X	X	X	X	X	X	244
TOTAL STAGE 7					3,301	6,465	192	3,301	6,465	0	0	0	0	0	0	782
TOTAL STAGES 1-7					10,830	17,708	526	10,830	17,708	7,294	7,795	22,988	352	879	49,812	2,062

STAGE 7 SHOULDER SCHEDULE

LOCATION STATION TO STATION			COMMENTS	PAVED SHOULDER WIDTH	SHOULDER DEPTH	PCC SHOULDER 12"	HMA SHOULDERS	AGG. SHLDRS, TY. A 8"	SHLDR RUMBLE STRIP	BIT MATLS (PRIME COAT)
				FT	INCH	SQ YD	TON	SQ YD	FOOT	GAL
STAGE 7										
817+80.00	TO	828+38.12	NB I-57 (I5764B) IL & IS	10	12	1176	X	X	1058	X
830+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	10	12	879	X	X	791	X
STAGE 7										
828+17.13	TO	828+37.13	SB I-57 (I5764A) IL & IS	10	12	22	X	X	20	X
830+18.63	TO	836+25.03	SB I-57 (I5764A) IL & IS	10	12	674	X	X	606	X
TOTAL STAGE 7						2,751	0	0	2,476	0
TOTAL GUARDRAIL SCHEDULE							626			
TOTAL STAGES 1-7						6,052	34,277	3,415	47,642	4,260

STAGE 7 REMOVAL SCHEDULE

LOCATION STATION TO STATION			COMMENTS	LANE WIDTH	PAVED SHOULDER WIDTH	HMA SURFACE REM, 3 3/4"	HMA SURF REM- BUTT JOINT	PVMT REM	PAVED SHLDR REM	HMA SURFACE REM, 2"
				FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
STAGE 7										
817+80.00	TO	828+38.12	NB I-57 (I5764B) IL & IS	12	10	X	X	1411	941	X
830+20.14	TO	838+11.42	NB I-57 (I5764B) DL & OS	12	10	X	X	1055	703	X
STAGE 7										
828+17.13	TO	828+37.13	SB I-57 (I5764A) IL & IS	12	10	X	X	27	18	X
830+18.63	TO	836+25.03	SB I-57 (I5764A) IL & IS	12	10	X	X	809	539	X
TOTAL STAGE 7						0	0	3,301	2,201	0
TOTAL STAGE 1-7						61,085	1,424	10,830	24,160	7,393