

SEEDING SCHEDULE

LOCATION STATION TO STATION	SEEDING, CLASS 2	SEEDING, CLASS 7	TEMP EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	PERIMETER EROSION BARRIER	EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	MOWING
	ACRE	ACRE	POUND	POUND	POUND	POUND	TON	ACRE	FOOT	SQ YD	FOOT	UNIT
NORTHBOUND I57 "B"												
818+00 TO 847+00	3.32	3.32	997	598.3	299.1	299.1	6.65	6.65	4700	16086.4	330	58
847+00 TO 867+00	2.2	2.2	660	396.3	198.1	198.1	4.4	4.4	600	10654.8	706	40
867+00 TO 880+50	1.49	1.49	447	268.1	134	134	2.98	2.98	800	7207.7	502	27
SUBTOTAL	7.0	7.0	2104	1262.7	631.2	631.2	14.0	14.0	6100	33949	1538	125
SOUTHBOUND I57 "A"												
830+00 TO 846+50	2.16	2.16	647	388.29	194.15	194.15	4.31	4.31	2400	10440.8	188	33
846+50 TO 870+00	3.53	3.53	1060	635.9	318	318	7.07	7.07	100	17099.4	708	47
870+00 TO 882+00	1.14	1.14	341	204.4	102.2	102.2	2.27	2.27	250	5494.7	622	24
882+00 TO 885+00	0.33	0.33	100	60.0	30.0	30.0	0.67	0.67	1050	1613.2	0	6
SUBTOTAL	7.2	7.2	2148	1288.6	644.4	644.4	14.3	14.3	3800	34648.1	1518	110
WESTBOUND/EASTBOUND I64												
2356+80 TO 2363+00	1.03	1.03	308	184.7	92.3	92.3	2.1	2.1	1575	4965.1	96	12
SUBTOTAL	1.0	1.0	308	184.7	92.3	92.3	2.1	2.1	1575	4965	96	12
EASTBOUND I64 TO SOUTHBOUND I57 "C"												
2364+00 TO 2378+50	1.59	1.59	478	286.7	143.3	143.3	3.19	3.19	500	7708.3	394	29
2378+50 TO 2396+00	1.8	1.8	541	324.6	162.3	162.3	3.61	3.61	350	8727.6	912	35
SUBTOTAL	3.4	3.4	1019	611.3	305.6	305.6	6.8	6.8	850	16435.9	1306	64
NORTHBOUND I57 TO WESTBOUND I64 "D"												
2364+50 TO 2378+50	1.85	1.85	556	333.7	166.8	166.8	3.71	3.71	150	8971.6	466	28
2378+50	3.04	3.04	913	547.7	273.9	273.9	6.09	6.09	850	14727	0	0
SUBTOTAL	4.9	4.9	1469	881.4	440.7	440.7	9.8	9.8	1000	23698.6	466	28
EASTBOUND I64 TO NORTHBOUND I57 "E"												
2+00 TO 20+50	3.86	3.86	1157	694.1	347	347	7.71	7.71	3500	18663	0	37
SUBTOTAL	3.9	3.9	1157	694.1	347.0	347.0	7.7	7.7	3500	18663.0	0	37
SOUTHBOUND I57 TO WESTBOUND I64 "F"												
2+00 TO 13+00	1.73	1.73	520	311.8	155.9	155.9	3.46	3.46	0	8384.8	0	22
SUBTOTAL	1.7	1.7	520	311.8	155.9	155.9	3.5	3.5	0	8384.8	0	22
TOTALS:	29.1	29.1	8725	5235	2618	2618	58.2	58.2	16825	140744	4924	398