

UNDERDRAIN REMOVAL

LOCATION				CONCRETE HEADWALL REMOVAL	PIPE UNDERDRAIN REMOVAL
I57 SB "A"				EACH	FOOT
830+00.	TO	885+00.	LT		5500
841+25.			LT	1	18
844+48.			LT	1	18
853+00.			LT	1	18
858+00.			LT	1	18
864+09.			LT	1	18
868+45.			LT	1	18
873+48.			LT	1	18
879+00.			LT	1	18
884+61.			LT	1	18
830+00.	TO	843+66.9	RT		1367
846+83.3	TO	869+83.1	RT		2300
871+93.3	TO	885+00.	RT		1307
839+70.			RT	1	18
848+61.			RT	1	18
853+00.			RT	1	18
858+47.			RT	1	18
864+89.			RT	1	18
873+48.			RT	1	18
879+00.			RT	1	18
I57 NB "B"					
817+30.	TO	828+39.	RT		1109
830+20.	TO	885+00.	RT		5480
839+25.			RT	1	18
843+48.			RT	1	18
853+44.			RT	1	18
884+59.			RT	1	18
817+30.	TO	828+33.	LT		1103
830+12.	TO	844+71.	LT		1459
847+03.	TO	866+77.	LT		1974
SUB				20	21958

LOCATION				CONCRETE HEADWALL REMOVAL	PIPE UNDERDRAIN REMOVAL
I57 NB "B"				EACH	FOOT
869+24.	TO	885+00.	LT		1576
818+75.			LT	1	18
838+13.			LT	1	18
841+86.			LT	1	18
844+00.			LT	1	18
852+48.			LT	1	18
857+24.			LT	1	18
872+00.			LT	1	18
877+90.			LT	1	18
884+69.			LT	1	18
I64 EB					
2360+00.	TO	2363+46	RT		346
			RT	1	18
2360+00.	TO	2363+46	LT		346
			LT	1	18
I64 WB					
2360+00.	TO	2363+46	RT		346
			RT	1	18
2360+00.	TO	2363+46	LT		346
			LT	1	18
I64 EB "C"					
2364+03.	TO	2398+72	RT		3469
2371+13.			RT	1	18
2391+18.			RT	1	18
2398+00.			RT	1	18
2363+46.	TO	2395+58	LT		3212
2372+80.			LT	1	18
2383+09.			LT	1	18
2388+92.			LT	1	18
SUB				19	9983

LOCATION				CONCRETE HEADWALL REMOVAL	PIPE UNDERDRAIN REMOVAL
I64 WB "D"				EACH	FOOT
2364+05.	TO	2385+75.	LT		2170
2388+50.	TO	2403+05.	LT		1455
2367+05.			LT	1	18
2372+50.			LT	1	18
2402+21.			LT	1	18
2364+05.	TO	2385+61	RT		2156
2388+30.	TO	2400+78	RT		1248
2366+87.			RT	1	18
2393+04.			RT	1	18
TOT				44	39060

*RIGHT AND LEFT BASED ON DIRECTION OF TRAVEL