

UNDERDRAINS

LOCATION				CONCRETE HEADWALL	PIPE UNDERDRAIN SPECIAL	PIPE UNDERDRAIN 4"	SHOULDER REMOVAL AND REPLACEMENT 5"
I57 SB "A"				EACH	FOOT	FOOT	FOOT
830+00.	TO	885+00.	LT	11	275	5500	0
830+00.	TO	843+66.9	RT	3	75	1367	1367
846+83.3	TO	869+83.1	RT	5	125	2300	2300
871+93.3	TO	885+00.	RT	3	75	1307	1307
SUB				22	550	10473	4974
I57 NB "B"							
817+30.	TO	828+39.	RT	2	50	1109	0
830+20.	TO	885+00.	RT	11	275	5480	5480
817+30.	TO	828+33.	LT	2	50	1103	0
830+12.	TO	844+71.	LT	3	75	1459	0
847+03.	TO	866+77.	LT	4	100	1974	0
869+24.	TO	885+00.	LT	3	75	1576	0
SUB				25	625	12701	5480
I64 EB							
2360+00	TO	2363+46	RT	1	25	346	346
2360+00	TO	2363+46	LT	1	25	346	0
SUB				2	50	692	346
I64 WB							
2360+00	TO	2363+46	RT	1	25	346	346
2360+00	TO	2363+46	LT	1	25	346	0
SUB				2	50	692	346
I64 EB "C"							
2364+03	TO	2398+72	RT	7	175	3469	3469
2363+46	TO	2395+58	LT	7	175	3212	0
SUB				14	350	6681	3469
I64 WB "D"							
2364+05.	TO	2385+75.	LT	4	100	2170	0
2388+50	TO	2403+05.	LT	3	75	1455	0
2364+05	TO	2385+61	RT	4	100	2156	2156
2388+30	TO	2400+78	RT	3	75	1248	1248
SUB				14	350	7029	3404
TOT				79	1975	38268	18019

•RIGHT AND LEFT BASED ON DIRECTION OF TRAVEL

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	UNDERDRAIN SCHEDULE			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\dot\k\elleyk\d\0278568\782	6-shrb-tp-sch-tes.dgn	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 78276
\$MODELNAME\$	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -										
	PLOT DATE = 2/7/2014	DATE -	REVISED -										