

## SUMMARY OF QUANTITIES - CONT

CODE NUMBER	ITEM DESCRIPTION	UNIT	CONSTRUCTION TYPE CODE: 0040 FUNDING: 80% FED 20% STATE
28200200	FILTER FABRIC	SQ YD	442
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	134
42001200	PAVEMENT FABRIC	SQ YD	134
44000100	PAVEMENT REMOVAL	SQ YD	134
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	217
50102400	CONCRETE REMOVAL	CU YD	73.2
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1840
54003000	CONCRETE BOX CULVERTS	CU YD	34.8
54011208	PRECAST CONCRETE BOX CULVERTS 12' X 8'	FOOT	50
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	31.25
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	286
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	8

\* SPECIALTY ITEM

FILE NAME :	USER NAME : portersu	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
g:\p-work\pedit\porter\03227201783	D-shiplandgn	DRAWN -	REVISED -			778	4B-2	HARDIN	19	4	
Defaults	PLOT SCALE = 100.0000 1/2 in.	CHECKED -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT CONTRACT NO. 78316			
	PLOT DATE = 1/28/2014	DATE -	REVISED -								