

SUMMARY OF QUANTITIES

FUNDING:	90% FED 10% STATE HSIP
LOCATION:	RURAL
ROUTE:	[L 34 (FAP 778)

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	90% FED 10% STATE HSIP		
				SALINE SAFETY 0021	POPE SAFETY 0021	HARDIN SAFETY 0021
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	611	21	348	242
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	848		359	489
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8655	294	4937	3424
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	27047	918	15429	10700
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1600		1600	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4	
63200310	GUARDRAIL REMOVAL	FOOT	1584		1584	
63301210	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1195	169	280	746
63301990	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1	EACH	17	2	3	12
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	60856	2066	34716	24074
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	1	1	1
67100100	MOBILIZATION	L SUM	1	0.2	0.4	0.4
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.2	0.4	0.4
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	0.5		0.5
* 72000100	SIGN PANEL - TYPE 1	SD FT	414	18	222	174

*** SPECIALTY ITEM**

FILE NAME *	USER NAME * kranz_jd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES 1 OF 2	F.A.P. RTE. 778	SECTION 09 SAFETY 2014-1	COUNTY VARIOUS	TOTAL SHEETS 11	SHEET NO. 4
Default	as:\p\work\p\videt\kranz_jd\20368242\7839	DRAWN -	REVISED -							
	PLOT SCALE = 94.4644 1/2 in.	CHECKED -	REVISED -							
	PLOT DATE = 1/23/2014	DATE -	REVISED -							
						SCALE:	SHEET OF	SHEETS STA.	TO STA.	ILLINOIS FED. AID PROJECT

REV. 4-15-14