

SHOULDER SCHEDULE

| LOCATION STA TO STA | HMA SHOULDERS 8" | BITUMINOUS MATERIALS (PRIME COAT) | SHOULDER RUMBLE STRIPS, 8 INCH | GRADING AND SHAPING SHOULDERS |
|--|------------------------|---|---|--|
| | SQ YD | GALLON | FOOT | UNIT |
| STA. 583+16.00 TO STA. 585+00.00 BK | 163.6 | 52.4 | 368.0 | 4.0 |
| STA. 585+02.63 AH TO STA. 592+45.90 BK | 660.7 | 211.4 | 1,487.0 | 15.0 |
| STA. 592+44.47 AH TO STA. 593+50.00 | 93.8 | 30.0 | 211.0 | 2.0 |
| SALINE CO TOTALS | 918.1 | 293.8 | 2,066.0 | 21.0 |
| STA. 593+50.00 TO STA. 612+55.10 BK | 1,693.4 | 541.9 | 3,810.0 | 38.0 |
| STA. 612+61.10 AH TO STA. 625+90.68 BK | 1,181.8 | 378.2 | 2,659.0 | 27.0 |
| STA. 625+85.58 AH TO STA. 626+10.82 BK | 22.4 | 7.2 | 50.0 | 1.0 |
| LT STA. 626+07.79 AH TO STA. 634+08.00 | 355.6 | 113.8 | 800.0 | 8.0 |
| RT STA. 626+07.79 AH TO STA. 634+24.00 | 362.8 | 116.1 | 816.0 | 8.0 |
| SN 076-2007 OMISSION | | | | |
| STA. 637+12.00 TO STA. 650+12.80 BK | 1,156.3 | 370.0 | 2,602.0 | 26.0 |
| STA. 650+09.34 AH TO STA. 664+03.96 BK | 1,239.7 | 396.7 | 2,789.0 | 28.0 |
| LT STA. 663+95.25 AH TO STA. 692+01.00 | 1,247.0 | 399.0 | 2,806.0 | 28.0 |
| RT STA. 663+95.25 AH TO STA. 692+20.00 | 1,255.4 | 401.7 | 2,825.0 | 28.0 |
| SN 076-0001 OMISSION | | | | |
| RT STA. 694+96.00 TO STA. 701+69.00 | 299.1 | 95.7 | 673.0 | 7.0 |
| LT STA. 695+98.00 TO STA. 701+69.00 | 253.8 | 81.2 | 571.0 | 6.0 |
| RT STA. 701+69.00 TO STA. 702+61.00 | 40.9 | 13.1 | 92.0 | 1.0 |
| LT STA. 701+69.00 TO STA. 702+81.00 | 49.8 | 15.9 | 112.0 | 1.0 |
| SN 076-2006 OMISSION | | | | |
| RT STA. 706+82.00 TO STA. 724+82.90 BK | 800.4 | 256.1 | 1,801.0 | 18.0 |
| LT STA. 707+55.00 TO STA. 724+82.90 BK | 768.0 | 245.8 | 1,728.0 | 17.0 |
| STA. 724+85.46 AH TO STA. 748+51.90 BK | 2,103.5 | 673.1 | 4,733.0 | 47.0 |
| STA. 748+54.52 AH TO STA. 771+94.00 BK | 2,079.5 | 665.4 | 4,679.0 | 47.0 |
| STA. 771+94.76 AH TO STA. 777+79.60 | 519.9 | 166.4 | 1,170.0 | 12.0 |
| POPE CO TOTALS | 15,429.3 | 4,937.3 | 34,716.0 | 348.0 |
| STA. 777+79.60 TO STA. 783+09.00 | 470.6 | 150.6 | 1,059.0 | 11.0 |
| SN 035-0004 OMISSION | | | | |
| STA. 784+61.00 TO STA. 790+00.00 BK | 479.1 | 153.3 | 1,078.0 | 11.0 |
| STA. 789+97.80 AH TO STA. 798+47.89 BK | 755.6 | 241.8 | 1,700.0 | 17.0 |
| STA. 798+52.22 AH TO STA. 804+48.00 | 529.6 | 169.5 | 1,192.0 | 12.0 |
| SN 035-0005 OMISSION | | | | |
| STA. 807+74.00 TO STA. 810+00.00 BK | 200.9 | 64.3 | 452.0 | 5.0 |
| STA. 810+06.37 AH TO STA. 818+55.20 BK | 754.5 | 241.4 | 1,698.0 | 17.0 |
| STA. 818+48.05 AH TO STA. 829+92.39 BK | 1,017.2 | 325.5 | 2,289.0 | 23.0 |
| STA. 829+85.24 AH TO STA. 830+22.50 BK | 33.1 | 10.6 | 75.0 | 1.0 |
| STA. 830+06.00 AH TO STA. 864+17.00 | 3,032.0 | 970.2 | 6,822.0 | 68.0 |
| SN 035-0006 OMISSION | | | | |
| STA. 865+23.00 TO STA. 872+81.01 BK | 673.8 | 215.6 | 1,516.0 | 15.0 |
| RT STA. 872+78.52 AH TO STA. 880+13.00 | 326.4 | 104.4 | 734.0 | 7.0 |
| LT STA. 872+78.52 AH TO STA. 880+35.00 | 336.2 | 107.6 | 756.0 | 8.0 |
| SN 035-7025 OMISSION | | | | |
| RT STA. 880+47.00 TO STA. 901+82.30 BK | 949.0 | 303.7 | 2,135.0 | 21.0 |
| LT STA. 880+67.00 TO STA. 901+82.30 BK | 940.1 | 300.8 | 2,115.0 | 21.0 |
| STA. 901+83.70 AH TO STA. 904+10.00 | 201.5 | 64.6 | 453.0 | 5.0 |
| HARDIN CO TOTALS | 10,699.6 | 3,423.9 | 24,074.0 | 242.0 |
| PROJECT TOTAL | 27,047.0 | 8,655.0 | 60,856.0 | 611.0 |

| | | | | | | | | | | | |
|-------------|--|------------|-----------|---|--------------------------------|---------------------------|------------------|---------|-----------------|--------------|--|
| FILE NAME = | USER NAME = kranzjc | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SCHEDULE - SHOULDER | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. | |
| Default | ct:\pw_work\pwidot\kranzjc\10368340\78395-sht-plan.dgn | DRAWN - | REVISED - | | | 778 | D9 SAFETY 2014-1 | VARIOUS | 11 | 7 | |
| | PLOT SCALE = 94.4444' / 1" = | CHECKED - | REVISED - | | | CONTRACT NO. 78395 | | | | | |
| | PLOT DATE = 1/28/2014 | DATE - | REVISED - | | | ILLINOIS FED. AID PROJECT | | | | | |