

# GUARDRAIL SCHEDULE

LOCATION STA TO STA	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' POSTS FOOT	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT EACH	GUARDRAIL REMOVAL FOOT	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1 EACH	GUARDRAIL MARKERS, TYPE B EACH	TERMINAL MARKER - DIRECT APPLIED EACH
RT STA. 583+16.00 TO STA. 583+64.00					1.0		
LT STA. 583+16.00 TO STA. 585+35.00				169.0	1.0		
SALINE CO TOTALS	0.0	0.0	0.0	169.0	2.0	0.0	0.0
RT STA. 632+08.00 TO STA. 634+24.00				166.0	1.0		
LT STA. 647+40.00 TO STA. 659+28.00	1,088.0	2.0	1,188.0			15.0	2.0
RT STA. 647+40.00 TO STA. 653+52.00	512.0	2.0				7.0	2.0
RT STA. 649+56.00 TO STA. 653+52.00			396.0				
RT STA. 690+56.00 TO STA. 692+20.00				114.0	1.0		
LT STA. 691+75.00 TO STA. 692+01.00					1.0		
POPE CO TOTALS	1,600.0	4.0	1,584.0	280.0	3.0	22.0	4.0
LT STA. 782+14.00 TO STA. 783+09.00				45.0	1.0		
RT STA. 782+14.00 TO STA. 783+09.00				45.0	1.0		
LT STA. 784+61.00 TO STA. 785+54.00				43.0	1.0		
RT STA. 784+61.00 TO STA. 785+54.00				43.0	1.0		
LT STA. 863+20.00 TO STA. 864+17.00				47.0	1.0		
RT STA. 863+39.00 TO STA. 864+17.00				28.0	1.0		
LT STA. 865+23.00 TO STA. 865+66.00					1.0		
RT STA. 865+23.00 TO STA. 866+15.00				42.0	1.0		
RT STA. 876+93.00 TO STA. 880+13.00				270.0	1.0		
LT STA. 880+13.00 TO STA. 880+35.00					1.0		
RT STA. 880+47.00 TO STA. 880+97.00					1.0		
LT STA. 880+67.00 TO STA. 883+00.00				183.0	1.0		
HARDIN CO TOTALS	0.0	0.0	0.0	746.0	12.0	0.0	0.0
PROJECT TOTAL	1,600.0	4.0	1,584.0	1,195.0	17.0	22.0	4.0