

PAVEMENT MARKING & MISC

STATION TO STATION				PAINT PAVT MARKING - LINE 4''			TEMP PAVT MARKING - LINE 4'' (INFO ONLY)	PAVEMENT MARKING REMOVAL	SHLDR RUMBLE STRIPS, 16 INCH	CENTER LINE - RUMBLE STRIP - 8''	SHORT TERM PAVEMENT MARKING	WORKZONE PAVEMENT MARKING REMOVAL
				4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH						
	1209+00	TO	1267+72			1,469						
	1273+95	TO	1310+64			918						
	1318+52	TO	1328+55			251						
	1329+82	TO	1340+21			260						
	1347+60	TO	1366+53			474						
CENTER LINE	1217+45	TO	1366+53				29,816			2,982		994
CENTER LINE	1209+00	TO	1215+00				600					
CENTER LINE	1366+53	TO	1368+28				175					
LEFT (EL)	1217+45	TO	1366+53	14,908			14,908	14,908				
LEFT (NPZ)	1217+45	TO	1219+00			155						
LEFT (NPZ)	1246+97	TO	1255+31			834						
LEFT (NPZ)	1267+72	TO	1285+51			1,779						
LEFT (NPZ)	1310+64	TO	1329+82			1,918						
LEFT (NPZ)	1340+21	TO	1358+32			1,811						
RIGHT (EL)	1217+45	TO	1366+53	14,908			14,908					
RIGHT (NPZ)	1235+78	TO	1245+12			934						
RIGHT (NPZ)	1256+58	TO	1273+95			1,737						
RIGHT (NPZ)	1300+30	TO	1318+52			1,822						
RIGHT (NPZ)	1328+55	TO	1347+60			1,905						
RIGHT (NPZ)	1365+87	TO	1366+53			66						
LEFT	1335+00	TO	1352+50					1,774				
RIGHT	1335+00	TO	1352+50					1,726				
CENTER LINE	1335+00	TO	1352+50						1,750			
SUB-TOTALS				29,816	12,961	3,372	59,632	5,228	3,500	1,750	2,982	994

EXISTING CULVERTS

LOCATION	EXISTING FILL HEIGHT OVER CULVERT	APPROVED FOR MTD CROSSING	NOTES
	FOOT		
IL 34			
SN 083-7013 (STA 1229+22)	2	YES	16" HMA PAVEMENT WITH ±8" OF PROCESSED MODIFIED SOIL
SN 083-7014 (STA 1252+50)	1	YES	±12" HMA PAVEMENT ONLY
SN 083-7015 (STA 1262+14)	4.7	YES	NORMAL TYPICAL SECTION
SN 083-7016 (STA 1295+60)	5	YES	NORMAL TYPICAL SECTION
SN 083-7017 (STA 1337+17)	2.6	YES	NORMAL TYPICAL SECTION
SN 083-7018 (STA 1360+24)	0.7	YES	±8.5" HMA PAVEMENT ONLY