

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY ITEM NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% LOCAL 0004	BRIDGE 80% FEDERAL 20% LOCAL 0011
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	26	26	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20	20	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	750.0	750.0	
20400800	FURNISHED EXCAVATION	CU YD	145.0	145.0	
20800150	TRENCH BACKFILL	CU YD	80.0	80.0	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	565	565	
21301072	EXPLORATION TRENCH 72 INCH DEPTH	FOOT	20	20	
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	11	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1,130	1,130	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	70	70	
28000400	PERIMETER EROSION BARRIER	FOOT	665	665	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
28100107	STONE RIPRAP, CLASS A4	SQ YD	440	440	
28200200	FILTER FABRIC	SQ YD	440	440	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	615	615	
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	615	615	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	310	310	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40603000	HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	90	90	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	55	55	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	45	45	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,255	1,255	
44000100	PAVEMENT REMOVAL	SQ YD	945	945	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50	
44000600	SIDEWALK REMOVAL	SQ FT	685	685	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	190.8		190.8
50300225	CONCRETE STRUCTURES	CU YD	62.1		62.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	217.3		217.3
50300260	BRIDGE DECK GROOVING	SQ YD	415		415

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
PAY ITEM NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	ROADWAY 80% FEDERAL 20% LOCAL 0004	BRIDGE 80% FEDERAL 20% LOCAL 0011
50300300	PROTECTIVE COAT	SQ YD	571		571
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	1,422		1,422
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	55,110		55,110
50900105	ALUMINUM RAILING, TYPE L	FOOT	61		61
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	480		480
51202305	DRIVING PILES	FOOT	480		480
51203200	TEST PILE METAL SHELLS	EACH	2		2
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS 1"	EACH	24		24
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	85	85	
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	83	83	
55100500	STORM SEWER REMOVAL 12"	FOOT	65	65	
55101200	STORM SEWER REMOVAL 24"	FOOT	20	20	
55101400	STORM SEWER REMOVAL 30"	FOOT	70	70	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	70		70
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	2	2	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.18	FOOT	100	100	
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	25	25	
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	42	42	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2,010	2,010	

COMPANY NAME: HRCGreen
PROJECT CONTACT: Kevin M. Artt
City of Rockford
1000 N. State Street
Rockford, IL 61101
PHONE: 815.398.3400
FAX: 815.398.3401
PLOT DRIVER: PLOTDRIVER
PLOT TABLE: PLOTTABLE



USER NAME	• wheed	DESIGNED	• KMA	REVISED	•
FILE NAME	• 86130854-Seq.dgn	DRAWN	• WJH	REVISED	•
PLOT SCALE	•	CHECKED	• RGD	REVISED	•
PLOT DATE	• 2/20/2014	DATE	• 2/20/14	REVISED	•

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

RAILROAD AVENUE OVER KEITH CREEK SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

M.S.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3259	11-00590-00-BR	WINNEBAGO	32	4
CONTRACT NO. 85607			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	