

COUNTY	SECTION	HWY.NO.	SHEET NO.
LASALLE	15-00326-00-WR	29	3 of 16

Contract # 89566

SUMMARY OF QUANTITIES - CONSTRUCTION TYPE CODE - 0004

S.P.	ITEM #	ITEM	UNIT	QUANTITY	S.P.	ITEM #	ITEM	UNIT	QUANTITY
*	20200500	EARTH EXCAVATION (WIDENING)	CU YD	1,921	*	70300100	SHORT TERM PAVEMENT MARKING	FOOT	3137
*	20400800	FURNISHED EXCAVATION	CU YD	3,518	†	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	50,980
	20800150	TRENCH BACKFILL	CU YD	80.4	†	78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	79
	21400100	GRADING AND SHAPING DITCHES	FOOT	200	†	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	19
	25000200	SEEDING, CLASS 2	ACRE	1.5	†	LR400005	CIR-FDR EMULSIFIED ASPHALT	GAL	67,000
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	135	†	LR400015	ADD ROCK	SQ YD	41,832
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	135	* †	LR400760	COLD IN-PLACE RECYCLING, 6.0"	SQ YD	41,832
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	135		Z0013798	CONSTRUCTION LAYOUT	L SUM	1
*	25100115	MULCH, METHOD 2	ACRE	1.5		X4060105	BITUMINOUS MATERIALS (PRIME COAT), SPECIAL	GAL	95
	28000305	TEMPORARY DITCH CHECKS	FOOT	1,408	†	X6310187	TRAFFIC BARRIER TERMINAL, TYPE 6 (MODIFIED)	EACH	4
	28000400	PERIMETER EROSION BARRIER	FOOT	320	†	X6330725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	68
	28000500	INLET AND PIPE PROTECTION	EACH	16		X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
	28100207	STONE RIPRAP, CLASS A4	TON	6	*	54260311	TRAVERSABLE PIPE GRATE	Foot	11
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	702					
*	35600670	HOT-MIX ASPHALT BASE COURSE WIDENING, 5"	SQ YD	27					
*	35600710	HOT-MIX ASPHALT BASE COURSE WIDENING, 8 1/2"	SQ YD	615					
*	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4,242					
	40600300	AGGREGATE (PRIME COAT)	TON	85					
*	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	523					
*	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	8,743					
*	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,790					
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	432					
	44000100	PAVEMENT REMOVAL	SQ YD	31					
	44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	59					
*	48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,611					
	50104400	CONCRETE HEADWALL REMOVAL	EACH	2					
*	50105220	PIPE CULVERT REMOVAL	FOOT	208					
*	542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	85					
*	542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	50					
*	542D5479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	43					
*	54261230	CONCRETE END SECTION, STANDARD 542001, 30", 1:2	EACH	2					
†	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,712.5					
†	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2					
†	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	19					
*	63200310	GUARDRAIL REMOVAL	FOOT	3,599					
	67100100	MOBILIZATION	L. SUM	1					

\* - SEE SPECIAL PROVISIONS

† - SPECIALTY ITEM

SUMMARY OF QUANTITIES