CONTRACT NO. 87567

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
10-00149-02-RS	LIVINGSTON	5	5

PROJECT NO. RS-0355(122)

SCHEDULE OF RESURFACING QUANTITIES

Unit weight Constant = 112.0 lbs./s.y./inch

LOCATION (QUANTITY)	LENGTH	AREA (SQ YD)	HMA SURF REMOVAL VAR DEPTH (SQ YD)	SHORT-TERM PAVT MARKING (FOOT)	WORK ZONE PAVT MK REM (SQ FT)	PAINT PVT MARKING LINE, 4" (FOOT)	BIT MATLS PR CT * (POUND)	BIT MATLS PR CT MC-30 (GALLON)	AGG PR CT (TON)	AREA REFL CR CONT (SQ YD)	LEVEL BINDER IL-9.5 N50 (TON)	BIT CONC SURF CSE "C" N50 (TON)	INCIDENTAL BIT SURF (TON)	AGG WEDGE SHOULDERS TYPE B (TON)
MAINLINE				*(2 Apps.)*	*(1 App.)*									
-0+30. to 1+20. (TAPER)	150	367	244	30	5	SCHEDULE ONE SHEET 3	83	-	-	122	7	31	-	15
1+20. to 282+90.	28170	68860	-	5634	939		15,494	-	138	68860	3,856	5,784	-	4278
282+90. to 284+65. (TAPER)	175	428	306	36	6		96	-	-	122	7	36	-	15
284+65. to 284+85. (053-3436)	20	49	49	4	1		11	-	-	49	-	4	-	-
284+85. to 286+60. (TAPER)	175	428	306	36	6		96	-	-	122	7	36	-	15
286+60. to 421+30.	13470	32927	-	2694	449		7,409	-	66	32927	1,844	2,766	-	2045
421+30. to 422+80. (TAPER)	150	367	244	30	5		83			122	7	31	-	15
TOTAL JOB LENGTH OR MAINLINE QUANTITY	42310.00	103424	1149	8464	1411	12275	23271	-	204	102324	5728	8688	-	6383
MISCELLANEOUS														
PRIVATE & COMMERCIAL ENTRANCES (26)	-	-	-	-	-	-	-	246.0	-	-	31	50	199.0	-
SIDEROAD INTERSECTIONS (16)	-	-	48.0	-	-	-	144.0	-	-	-	64	64	300.0	-
M.B.T.O.'s (16)	-	-	-	-	-	-	-	-	-	-	17	43	-	-
TOTALS OF MAINLINE & MISC.	42,310	103,424	1,197	8,464	1,411	12,275	23,415	246	204	102,324	5,840	8,845	499	6,383

* BITUMINOUS MATERIALS (PRIME COAT) SHALL BE IN ACCORDANCE WITH THE TABLE SHOWN IN ARTICLE 406.02 OF THE STANDARD SPECIFICATIONS.

\\chd2010\ch\COWorkNROAD\Projects\00149RS2-Flanagan-Gridley\Planning\EstCost-ResurfSched-FlanGridley.xlsj\SchedResurfQty