

PAY ITEM NUMBER	ITEM DESCRIPTION (1 OF 4)	UNIT OF MEASURE	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	295.0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	58.0
20101000	TEMPORARY FENCE	FOOT	384.0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	890.0
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	2134.0
Δ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6614.0
Δ 25000110	SEEDING, CLASS 1A	ACRE	0.50
Δ 25000210	SEEDING, CLASS 2A	ACRE	1.0
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	125.0
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	125.0
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	125.0
Δ 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	6614.0
Δ 25200110	SODDING, SALT TOLERANT	SQ YD	108.0
Δ 25200200	SUPPLEMENTAL WATERING	UNIT	0.6
28000305	TEMPORARY DITCH CHECK	FOOT	950.0
28000315	AGGREGATE DITCH CHECK	TON	49.0
28000400	PERIMETER EROSION BARRIER	FOOT	985.0
28000500	INLET & PIPE PROTECTION	EACH	25.0
28000510	INLET FILTERS	EACH	20.0
28001200	TEMPORARY HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1301.0
28100105	STONE RIP-RAP, CLASS A3	SQ YD	64.0
28100107	STONE RIP-RAP, CLASS A4	SQ YD	420.0
28200200	FILTER FABRIC	SQ YD	420.0
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	14833.0
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	889.0
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3000.0
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	12.0
42001200	PAVEMENT FABRIC	SQ YD	11322.0
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	12580.0
42300600	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 10 INCH	SQ YD	93.0
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	27124.0
42400800	DETECTABLE WARNINGS	SQ FT	141.0

PAY ITEM NUMBER	ITEM DESCRIPTION (2 OF 4)	UNIT OF MEASURE	QUANTITY
44000100	PAVEMENT REMOVAL	SQ YD	12326.0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	132.0
44000300	CURB REMOVAL	FOOT	299.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	7295.0
44000600	SIDEWALK REMOVAL	SQ FT	18399.0
44003100	MEDIAN REMOVAL	SQ FT	1718.0
44004250	PAVED SHOULDER REMOVAL	SQ YD	422.0
48301000	PROTECTIVE COAT	SQ YD	15580.0
50104400	CONCRETE HEADWALL REMOVAL	EACH	4.0
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1.0
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4.0
55100500	STORM SEWER REMOVAL 12"	FOOT	958.0
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	126.0
60100050	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1.0
60107700	PIPE UNDERDRAINS 6"	FOOT	3590.0
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	34.0
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2.0
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1.0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3.0
60500040	REMOVING MANHOLES	EACH	4.0
60500060	REMOVING INLETS	EACH	10.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1925.0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3609.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4144.0
60625600	ISLAND PAVEMENT, 6"	SQ YD	40.0
Δ 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	300.0
Δ 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2.0
Δ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2.0
63200310	GUARDRAIL REMOVAL	FOOT	300.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.0
67100100	MOBILIZATION	L SUM	1.0
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	110.0

FILE NAME *	USER NAME * USER*	DESIGNED - JLH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STERLING AVENUE SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN - JAL	REVISED -		6586	05-00010-00-PV	PEORIA	86	5			
SHT_PLAN		CHECKED - JLH	REVISED -		STERLING AVENUE			CONTRACT NO. 89386				
		DATE - JAN 2014	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.	FED ROAD DIST NO. 4 ILLINOIS FED. AID PROJECT M-5314 100P