

PAVEMENT MARKING SCHEDULE		78009000	78009004		78009006	78009008		78009012	78009024	78100100	X7830068	X7830070	X7830074	X7830076	X7830078	X7830090
LOCATION	LENGTH	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	GROOVING FOR RECESSED PAVEMENT MARKING 9"	GROOVING FOR RECESSED PAVEMENT MARKING 13"	GROOVING FOR RECESSED PAVEMENT MARKING 25"
		WHITE SOLID	YELLOW SOLID	WHITE SOLID	WHITE SKIP DASH	WHITE SOLID	WHITE SKIP DASH	YELLOW SOLID	WHITE SOLID	CRYSTAL, ONE-WAY	AREA	LENGTH	LENGTH	LENGTH	LENGTH	LENGTH
STATION TO STATION		FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT
STA. 25+14.28 TO STA. 25+47.96		33.68		151.0				20.6				151.0			20.6	
STA. 25+14.28 TO STA. 26+07.47		93.19			193.9	50.0				16.6	5.0	193.9	50.0			16.6
STA. 26+07.47 TO STA. 31+26.38		518.91	31.2	1046.1	1037.8	260.0	320.0	50.0		26.0	31.2	2083.9	260.0	370.0		
STA. 31+26.38 TO STA. 39+93.46		867.08		1734.2	1734.2	430.0				43.0		3468.3	430.0			
STA. 39+93.46 TO STA. 44+67.21		473.75	78.0	828.6	1050.8	270.0	650.7	150.0		83.0	24.0	1879.4	270.0	800.7		83.0
SUBTOTAL		-	-	3759.9	4016.7	-	970.7	200.0	-	-	-	-	-	-	-	-
TOTAL		110.0	-	7777.0	-	1010.0	1171.0	21.0	100.0	98.0	110.0	7777.0	1010.0	1171.0	21.0	100.0

LOCATING UNDERGROUND UTILITIES				X0327235
LOCATION	FIBER OPTIC	TELEPHONE	SANITARY	TOTAL
STATION	FOOT	FOOT	FOOT	FOOT
STA. 25+87 RT	5.0	5.0		10.0
STA. 26+12 RT	5.0			5.0
STA. 27+00 RT	5.0			5.0
STA. 27+75 RT	5.0	5.0	10.0	20.0
STA. 30+17 RT	5.0			5.0
STA. 31+00 RT		5.0		5.0
STA. 32+00 RT		5.0		5.0
STA. 33+00 RT		5.0		5.0
STA. 33+33 RT	5.0			5.0
STA. 36+76 RT	5.0			5.0
STA. 38+35 RT		10.0		10.0
STA. 40+00 RT	5.0	5.0		10.0
STA. 41+00 RT	5.0	5.0		10.0
STA. 41+31 RT	5.0			5.0
STA. 42+30 RT	5.0	5.0		10.0
STA. 43+35 RT		10.0		10.0
TOTAL				125.0

TRAFFIC CONTROL AND PROTECTION (SPECIAL)		X7010216
LOCATION	UNIT	
STATION	LSUM	
ENTIRE JOB	1.0	
TOTAL	1.0	

CONSTRUCTION LAYOUT		Z0013798
LOCATION	UNIT	
STATION	LSUM	
ENTIRE JOB	1.0	
TOTAL	1.0	

ISLAND REMOVAL				X4402805
LOCATION	LENGTH	WIDTH	AREA	
STATION TO STATION	FOOT	FOOT	SQ FT	
STA. 44+45.52 TO STA. 44+65.81	20.3	VARIES	232.5	
STA. 44+48.50 TO STA. 44+64.16	15.7	VARIES	134.9	
TOTAL			368.0	

ABANDON AND FILL EXISTING STORM SEWER		X5509900
LOCATION	LENGTH	
STA. AND O/S TO STA. AND O/S	FOOT	
STA. 41+33.83, 35.5' LT TO STA. 41+33.86, 94.4' LT	58.9	
TOTAL	59.0	