



ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	525
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50
20700110	POROUS GRANULAR EMBANKMENT	TON	100
20800150	TRENCH BACKFILL	CU YD	10
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	792
25100630	EROSION CONTROL BLANKET	SQ YD	282
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	55
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	17
28000305	TEMPORARY DITCH CHECKS	FOOT	21
28000400	PERIMETER EROSION BARRIER	FOOT	860
28000510	INLET FILTERS	EACH	4
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	1420
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	35
42000110	PORTLAND CEMENT CONCRETE PAVEMENT 6 1/2"	SQ YD	1357
42001300	PROTECTIVE COAT	SQ YD	2170
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	64
44000100	PAVEMENT REMOVAL	SQ YD	1044
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	778
44000600	SIDEWALK REMOVAL	SQ FT	74
44004000	PAVED DITCH REMOVAL	FOOT	43
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5370
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	67
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2
60500040	REMOVING MANHOLES	EACH	1
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5200
72000100	SIGN PANEL - TYPE 1	SQ FT	18
72900100	METAL POST - TYPE A	FOOT	27
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	35445
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	1098
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	39
X0324058	OUTLET SPECIAL	EACH	1
X4200840	PORTLAND CEMENT CONCRETE INLAY, 4"	SQ YD	743
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1
X6061815	COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)	FOOT	169
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
X7240300	SIGN REMOVAL	EACH	3
* XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	67
XX004450	BITUMINOUS SURFACE TREATMENT, A-2 SPECIAL	SQ YD	116656
XX006343	SEEDING (COMPLETE)	SQ YD	792
XX006529	CONCRETE CURB AND GUTTER END OUTLET SPECIAL	EACH	3
XX007371	PORTLAND CEMENT CONCRETE PAVEMENT, FURNISHED	CU YD	83
XX008871	MULCH	SQ YD	455
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
LR400005	CIR-FDR EMULSIFIED ASPHALT	GALLON	258471
LR400760	COLD IN-PLACE RECYCLING, 6.0"	SQ YD	116656
LR403300	SURFACE PROFILE MILLING	SQ YD	116656

* SPECIALTY ITEM

DATE	BY
1/21/2014	JMM
1/21/2014	JMM
1/21/2014	KAB

FILE NAME	USER NAME	DESIGNED	REVISOR
T:\11 Jobs\11-00101\11-00101-Road\Sheet\11-00101-Road.dwg	jmm	JMM	
		DRAWN	REVISOR
		JMM	
		CHECKED	REVISOR
		KAB	
		DATE	REVISOR
		1/21/2014	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TENNESSEE BLACKTOP (CH 11)
SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1434	11-00101-00-RS	McDONOUGH	33	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			RS 1434 (106)	

CONTRACT NO. 089607