

EARTHWORK

LOCATION	EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
CH 2				
STA 10+74 TO STA 14+80	55	41	30	11
TOTAL	55	41	30	11

SHRINKAGE = 25%

SEEDING, CLASS 2 (SPECIAL)

LOCATION	ACRE
LT STA 11+28.00 TO STA 14+88.00	0.03
RT STA 11+66.00 TO STA 12+66.00	0.01
RT STA 12+80.00 TO STA 14+82.00	0.01
TOTAL	0.05

PAVED SHOULDER REMOVAL

LOCATION	SQ YD
LT STA 12+12.07 TO STA 14+72.24	87.29
RT STA 12+12.58 TO STA 14+72.71	86.72
TOTAL	174.01

COMBINATION CURB AND GUTTER REMOVAL

LOCATION	FOOT
LT STA 11+57.98 TO STA 14+72.47	314.49
RT STA 11+82.04 TO STA 12+57.35	75.31
RT STA 12+88.85 TO STA 14+72.92	184.07
TOTAL	573.87

GUARDRAIL REMOVAL

LOCATION	FOOT
LT STA 110+55.69 TO STA 111+55.69	100
LT STA 116+77.09 TO STA 117+77.09	100
RT STA 110+55.69 TO STA 111+55.69	100
RT STA 116+77.09 TO STA 117+77.09	100
TOTAL	400

HOT-MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH

LOCATION	WIDTH FOOT	SQ YD
STA 11+14.24 TO STA 64+81.18	24	14,311.84
STA 82+65.18 TO STA 110+08.19	22	6,705.14
TOTAL		21,016.98

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	WIDTH FOOT	SQ YD
STA 10+74.24 TO STA 11+14.24	24	106.67
STA 64+81.18 TO STA 65+21.18	24	106.67
STA 82+25.18 TO STA 82+65.18	22	97.78
STA 110+08.19 TO STA 110+68.19	22	146.67
STA 116+67.19 TO STA 117+27.19	22	146.67
STA 129+40.00 TO STA 130+00.00	22	146.67
TOTAL		751.13

TEMPORARY RAMP

LOCATION	LENGTH FT	QTY SQ YD
STA 10+74.24 TO STA 10+79.24	5	13.33
STA 65+16.18 TO STA 65+21.18	5	13.33
STA 82+25.18 TO STA 82+30.18	5	12.22
STA 110+63.19 TO STA 110+68.19	5	12.22
STA 116+67.19 TO STA 116+72.19	5	12.22
STA 129+95.00 TO STA 130+00.00	5	12.22
TOTAL		75.54

HOT-MIX ASPHALT SURFACE REMOVAL, 6" *

LOCATION	SQ YD
LT STA 110+35.00 TO STA 111+68.19	103.59
RT STA 117+75.00 TO STA 128+61.00	844.67
TOTAL	948.26

* THIS ITEM INCLUDES REMOVAL OF 3" TO 5" OF EXISTING HMA SURFACE AND 3" TO 1" OF EXISTING AGGREGATE BASE.

HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N50

LOCATION	THICKNESS	TON
LT STA 110+35.00 TO STA 111+68.19	6"	34.81
RT STA 117+75.00 TO STA 128+61.00	6"	283.81
TOTAL		318.62