

ENTRANCES, MAIL BOX TURNOUTS AND SIDE ROADS

LOCATION	TYPE	WIDTH	LENGTH	AGGREGATE SURFACE COURSE	AGGREGATE BASE COURSE	HMA SURFACE REMOVAL - BUTT JOINT	PCC SURFACE REMOVAL - BUTT JOINT	BITUMINOUS MATERIALS (PRIME COAT)	INCIDENTAL HMA SURFACING	
				TON	TON	SQ YD	SQ YD	GALLON	TON	
RT STA 100+82	PE/MB	CONC	16	10			11.11	4.80	6.05	
RT STA 102+18	PE/MB	CONC	19	15			16.67	7.09	8.93	
RT STA 102+95	PE/MB	HMA	17	15				5.91	7.45	
RT STA 103+19	PE	HMA	24	15			26.67	5.97	7.52	
RT STA 105+00	MB	HMA						2.17	2.73	
RT STA 106+00	PE/MB	AGG	21	15	1.01	15.87		1.81	2.28	
RT STA 107+07	PE/MB	HMA	16	15				5.93	7.48	
RT STA 107+50	MB	HMA						2.16	2.72	
RT STA 109+50	PE/MB	HMA	19	15				7.29	9.18	
RT STA 121+50	FE	AGG	16	10	2.47					
TOTAL					32.73	272.00	408.33	55.56	192.32	242.3

STEEL PLATE BEAM GUARD RAIL, TYPE A 6 FOOT POSTS

LOCATION	FOOT
LT STA 111+00.04 TO STA 111+12.54	12.5
LT STA 117+20.84 TO STA 118+45.84	125.0
RT STA 110+25.04 TO STA 111+12.54	87.5
RT STA 117+20.84 TO STA 117+58.34	37.5
TOTAL	262.5

TRAFFIC BARRIER TERMINAL, TYPE 6

LOCATION	EACH
LT STA 111+12.54 TO STA 111+56.29	1
LT STA 116+77.09 TO STA 117+20.84	1
RT STA 111+12.54 TO STA 111+56.29	1
RT STA 116+77.09 TO STA 117+20.84	1
TOTAL	4

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

LOCATION	EACH
LT STA 110+50.04 TO STA 111+00.04	1
LT STA 118+45.84 TO STA 118+95.84	1
RT STA 109+75.04 TO STA 110+25.04	1
RT STA 117+58.34 TO STA 118+08.34	1
TOTAL	4

SHORT-TERM PAVEMENT MARKING

LOCATION	APPLICATIONS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
		FOOT	SQ FT
STA 10+30.00 TO STA 65+21.18	4	2,208	184
STA 82+75.18 TO STA 111+68.19	4	1,168	98
STA 116+67.19 TO STA 129+84.81	4	528	44
TOTAL		3,904	326

GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
LT STA 111+00.04 TO STA 118+45.84	10
RT STA 110+25.04 TO STA 117+58.34	10
TOTAL	20

TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH
LT STA 110+50.04	1
LT STA 118+95.84	1
RT STA 109+75.04	1
RT STA 118+08.34	1
TOTAL	4

*93014



JOB : 2298
 FILE NAME : 2298.dgn
 PLOT SCALE : 20,000 / IN.
 PLOT DATE : 11/26/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 11/15/2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

LOGAN COUNTY
 CH 2 IMPROVEMENTS

SCHEDULE OF QUANTITIES

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 2	11-00311-02-RS	LOGAN	37	16

CONTRACT NO. 11-00311-02-RS

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT