

PAVEMENT MARKING

LOCATION	PAIN T PAVEMENT MARKING - LINE 4" (WHITE)	PAIN T PAVEMENT MARKING - LINE 4" (YELLOW)	TOTAL PAINT PAVEMENT MARKING - LINE 4"
	FOOT	FOOT	FOOT
NICHOLSON RD - FAS 559 (CH 2)			
LT. EDGE - WHITE (4")			
STA. 10+30.00 TO STA. 65+21.18	5,491.18		5,491.18
STA. 82+75.18 TO STA. 111+68.19	2,893.01		2,893.01
STA. 116+67.19 TO STA. 129+84.81	1,317.62		1,317.62
RT. EDGE - WHITE (4")			
STA. 10+30.00 TO STA. 65+21.18	5,491.18		5,491.18
STA. 82+75.18 TO STA. 111+68.19	2,893.01		2,893.01
STA. 116+67.19 TO STA. 129+84.81	1,317.62		1,317.62
CENTERLINE SKIP DASH - YELLOW (4")			
STA. 10+30.00 TO STA. 65+21.18		1,380.00	1,380.00
STA. 82+75.18 TO STA. 101+75.31		480.00	480.00
STA. 128+46.31 TO STA. 130+00.00		40.00	40.00
LT. NO PASSING - YELLOW (4")			
STA. 10+74.24 TO STA. 19+26.00		851.76	851.76
STA. 101+75.31 TO STA. 130+00.00		2,824.69	2,824.69
RT. NO PASSING - YELLOW (4")			
STA. 10+74.24 TO STA. 14+81.00		406.76	406.76
STA. 63+50.00 TO STA. 65+21.18		171.18	171.18
STA. 91+00.00 TO STA. 128+46.31		3,746.31	3,746.31
TOTAL	19,403.62	9,900.70	29,304.32

*93614



JOB # 2298	DESIGNED - NAK	REVISED -
FILE NAME + 2298soq.dgn	DRAWN - SJS	REVISED -
PLOT SCALE + 20.0000' / IN.	CHECKED - NAK	REVISED -
PLOT DATE + 11/25/2013	DATE - 11/15/2013	REVISED -

**LOGAN COUNTY
CH 2 IMPROVEMENTS**

SCHEDULE OF QUANTITIES

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 2	11-00311-02-R5	LOGAN	37	17

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. *