

CODED NO	DESCRIPTION	UNIT	TOTAL QUANTITY	FEDERAL PARTICIPATION	NON-FEDERAL PARTICIPATION
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20	20	-
20200100	EARTH EXCAVATION	CU YD	285	281	4
20400800	FURNISHED EXCAVATION	CU YD	510	510	-
20800150	TRENCH BACKFILL	CU YD	281	281	-
25000100	SEEDING, CLASS 1	ACRE	0.5	0.5	-
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	40	40	-
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40	40	-
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	40	40	-
25100105	MULCH, METHOD 1	ACRE	0.5	0.5	-
28000305	TEMPORARY DITCH CHECKS	FOOT	64	64	-
28000400	PERIMETER EROSION BARRIER	FOOT	247	247	-
28000500	INLET AND PIPE PROTECTION	EACH	35	35	-
28100107	STONE RIPRAP, CLASS A4	SQ YD	39	39	-
28200200	FILTER FABRIC	SQ YD	39	39	-
* 31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	935	935	-
* 40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	478	478	-
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	223	223	-
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	12,671	12,210	461
42400800	DETECTABLE WARNINGS	SQ FT	120	100	20
44000100	PAVEMENT REMOVAL	SQ YD	683	683	-
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	186	186	-
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	397	397	-
44000600	SIDEWALK REMOVAL	SQ FT	218	122	96
* 44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	24	24	-
50105220	PIPE CULVERT REMOVAL	FOOT	32	32	-
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1	1	-
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	18	18	-
54200217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	6	6	-
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	-
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	483	483	-
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	203	203	-
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	288	288	-
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	368	368	-
55100500	STORM SEWER REMOVAL 12"	FOOT	217	217	-
55100700	STORM SEWER REMOVAL 15"	FOOT	355	355	-
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	-
60218600	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 4 FRAME AND GRATE	EACH	8	8	-
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	2	2	-

* SPECIALTY ITEMS

FILE NAME : 1003796-500.dgn	USER NAME : kostermler	DESIGNED - KMO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - KMO	REVISED -			10-00036-00-SW	RANDOLPH	52	3	
		CHECKED -	REVISED -			CONTRACT NO. #97517				
		DATE -	REVISED -			SCALE:	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT