

SIDEWALK SCHEDULE				
LOCATION				PCC SIDEWALK, 4"
				SO FT
STATION	TO	STATION	ROAD	
HILLCREST DRIVE				
0+00.00	RMP to	0+00.00	RMP	97
0+20.30	RT to	0+92.29	RT	460
0+92.29	RMP to	1+03.34	RMP	51
1+17.50	RMP to	1+28.53	RMP	51
1+28.53	RT to	1+48.09	RT	98
1+48.09	RT to	1+58.09	RT	45
1+58.09	RT to	1+68.09	RT	40
1+68.09	RT to	1+78.09	RT	45
1+78.09	RT to	2+35.29	RT	286
2+35.29	RMP to	2+46.30	RMP	51
2+65.65	RMP to	2+76.64	RMP	51
2+76.64	RT to	3+60.66	RT	420
3+60.66	RMP to	3+71.67	RMP	51
3+89.67	RMP to	4+00.68	RMP	51
4+00.68	RT to	4+40.28	RT	198
4+40.28	RMP to	4+51.32	RMP	51
4+63.26	RMP to	4+74.26	RMP	51
4+74.26	RT to	4+79.26	RT	23
4+79.26	RT to	5+24.26	RT	180
5+24.26	RT to	5+34.26	RT	45
5+34.26	RT to	6+34.58	RT	502
6+34.58	RMP to	6+45.53	RMP	51
6+68.00	RMP to	6+78.94	RMP	51
6+78.94	RT to	6+96.39	RT	91
6+96.39	RMP to	7+09.02	RMP	78
7+38.94	RMP to	7+52.07	RMP	81
7+52.07	RT to	8+15.00	RT	315
8+15.00	RT to	8+25.00	RT	45
8+25.00	RT to	9+50.00	RT	500
9+50.00	RT to	9+60.00	RT	45
9+60.00	RT to	14+11.10	RT	2256
14+11.10	RMP to	14+21.92	RMP	52
14+54.24	RMP to	14+65.07	RMP	52
14+65.07	RT to	18+71.30	RT	2031
18+71.30	RMP to	18+86.95	RMP	65
19+20.91	RMP to	19+30.76	RMP	48
19+30.76	RT to	23+22.40	RT	1958
23+22.40	RMP to	23+43.65	RMP	82
23+97.66	RMP to	24+12.65	RMP	64
24+12.65	RT to	25+21.90	RT	567
SUB-TOTAL:				11275
BRADBURY LANE				
0+25.31	RT to	0+36.89	RT	52
0+36.89	RT to	2+07.77	RT	883
SUB-TOTAL:				935
ENTRANCE TO PUBLIC POOL - (NON PARTICIPATING)				
BEGIN	to	END		461
SUB-TOTAL:				461
TOTAL:				12671
PAY TOTAL:				12671

PAVING SCHEDULE				
LOCATION			SUBBASE GRANULAR MATERIAL, TYPE A 4"	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"
STATION	TO	STATION	SO YD	SO YD
HILLCREST DRIVE				
-0+22.31	TO	-0+18.66	5	2
0+16.31	TO	0+19.79	4	2
0+90.34	TO	1+30.50	12	10
2+53.32	TO	2+76.66	12	10
3+60.67	TO	4+00.67	12	10
4+40.31	TO	4+74.26	10	8
6+34.54	TO	6+78.98	12	10
6+86.29	TO	7+10.66	22	10
7+37.99	TO	7+41.55	4	2
9+23.51	TO	14+23.66	248	-
9+23.51	TO	14+10.19	-	108
14+38.00		SYCAMORE	98	82
14+65.97	TO	23+36.68	426	194
24+07.79	TO	25+43.00	70	30
SUB-TOTAL:			935	478
TOTAL:			935	478

PAVEMENT MARKING SCHEDULE						
LOCATION					PAINT PAVEMENT MARKING - LINE 6"	PAINT PAVEMENT MARKING - LINE 12"
STATION	TO	STATION	LOCATION	TYPE	FOOT	FOOT
HILLCREST DRIVE						
-0+18.12	TO	0+16.38	INTERSECTION	Solid White	69	-
-0+18.12	TO	0+16.38	INTERSECTION	Solid White	-	12
7+10.13	TO	7+38.50	INTERSECTION	Solid White	57	-
7+10.13	TO	7+38.50	INTERSECTION	Solid White	-	12
14+22.05	TO	14+54.12	INTERSECTION	Solid White	65	-
14+22.05	TO	14+54.12	INTERSECTION	Solid White	-	13
23+44.19	TO	23+98.71	INTERSECTION	Solid White	110	-
23+44.19	TO	23+98.71	INTERSECTION	Solid White	-	19
SUB-TOTAL:					301	56
BRADBURY LANE						
-0+13.4	TO	0+28.73	INTERSECTION	Solid White	80	-
SUB-TOTAL:					80	0
ENTRANCE TO PUBLIC POOL - (NON PARTICIPATING)						
LT	TO	RT	CROSSING	Solid White	46	-
SUB-TOTAL:					46	0
TOTAL:					427	56

DETECTABLE WARNING SCHEDULE		
LOCATION	DETECTABLE WARNING	
STATION	SO FT	
HILLCREST DRIVE		
-0+20.72	RT	10
0+18.33	RT	10
7+06.79	RT	10
7+41.10	RT	10
14+17.10	RT	10
14+59.07	RT	10
23+36.06	RT	10
24+06.55	RT	10
25+13.39	RT	10
SUB-TOTAL:		90
BRADBURY LANE		
0+30.89	RT	10
SUB-TOTAL:		10
ENTRANCE TO PUBLIC POOL - (NON PARTICIPATING)		
	LT	10
	RT	10
SUB-TOTAL:		20
TOTAL:		120

CURB AND GUTTER SCHEDULE						
LOCATION				COMBINATION CURB AND GUTTER, TYPE B-6.1B	CLASS SI CONCRETE (OUTLET)	
STATION	TO	STATION	FOOT	C.Y.		
HILLCREST DRIVE						
-0+22.31	22.16	RT TO	-0+18.66	29.57	RT	9
0+16.31	29.63	RT TO	0+19.79	22.34	RT	8
0+90.34	15.03	RT TO	1+30.50	15.02	RT	40
2+35.32	15.26	RT TO	2+76.66	15.26	RT	41
3+60.67	15.54	RT TO	4+00.67	15.54	RT	40
4+40.31	15.65	RT TO	4+74.26	15.63	RT	34
6+34.54	15.68	RT TO	6+78.98	15.94	RT	44
6+86.29	16.14	RT TO	7+10.66	41.60	RT	41
7+37.99	32.31	RT TO	7+41.55	24.18	RT	9
9+23.51	16.45	RT TO	14+23.66	32.59	RT	514
14+51.47	32.72	RT TO	23+55.80	44.77	RT	935
23+88.46	43.61	RT TO	23+38.00	13.50	RT	168
23+38.00		RT TO	25+43.00		RT	-
SUB-TOTAL:				1883		0.5
TOTAL:				1883		0.5

RIPRAP SCHEDULE				
LOCATION		STONE RIPRAP, CLASS A4	FILTER FABRIC	
STATION	TO	SO YD	SO YD	
HILLCREST DRIVE				
11+50.00	21.94	RT	18	18
18+81.45	35.28	RT	12	12
21+25.00	27.00	RT	6	6
25+43.00	12.00	RT	3	3
SUB-TOTAL:		39	39	
TOTAL:		39	39	