

STORM SEWER AND PIPE CULVERT SCHEDULE																	
LOCATION						PIPE CULVERTS, CLASS D, TYPE 1, 12"	STORM SEWERS, CLASS A, TYPE 1, 12"	STORM SEWERS, CLASS A, TYPE 1, 15"	STORM SEWERS, CLASS A, TYPE 1, 18"	STORM SEWERS, CLASS A, TYPE 1, 24"	PRECAST REINFORCED CONCRETE FLARED END SECTION, 24"	PRECAST CONCRETE BOX CULVERTS, 4' x 4'	BOX CULVERT END SECTIONS, CULVERT NO. 1	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL, 12"	STORM SEWER REMOVAL, 15"	TRENCH BACKFILL
STATION	TO	STATION				FOOT	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	EACH	FOOT	FOOT	FOOT	CU YD
HILLCREST DRIVE																	
6+89.30	15.38	RT TO	7+03.92	23.03	RT	-	-	14	-	-	-	-	-	-	-	-	2
7+11.10	38.59	RT TO	7+03.92	23.03	RT	-	-	15	-	-	-	-	-	-	-	-	2
8+88.12	20.02	RT TO	11+08.17	20.43	RT	-	-	-	-	-	-	-	-	-	-	220	-
8+88.12	20.02	RT TO	9+25.00	15.65	RT	-	-	36	-	-	-	-	-	-	-	-	7
9+25.00	15.65	RT TO	9+50.00	14.93	RT	-	-	23	-	-	-	-	-	-	-	-	5
9+50.00	14.93	RT TO	10+50.00	12.75	RT	-	-	-	98	-	-	-	-	-	-	-	21
10+50.00	12.75	RT TO	11+10.26	14.81	RT	-	-	-	58	-	-	-	-	-	-	-	12
10+50.00	26.58	RT TO	10+50.00	12.75	RT	-	-	11	-	-	-	-	-	-	-	-	2
11+08.17	20.43	RT TO	11+51.27	23.96	LT	-	-	-	-	-	-	-	-	-	-	66	-
11+10.26	14.81	RT TO	11+50.00	12.75	RT	-	-	-	37	-	-	-	-	-	-	-	9
11+50.00	12.75	RT TO	11+50.00	21.94	LT	-	-	-	-	27	-	-	-	-	-	-	7
11+50.00	21.94	LT				-	-	-	-	1	-	-	-	-	-	-	-
12+12.50	12.75	RT TO	11+50.00	12.75	RT	-	-	60	-	-	-	-	-	-	-	-	14
14+11.09	12.75	RT TO	14+65.97	12.75	RT	-	53	-	-	-	-	-	-	-	-	-	9
14+11.09	22.82	RT TO	16+27.98	21.07	RT	-	-	-	-	-	-	-	-	217	-	-	-
14+11.09	25.54	RT TO	14+11.09	12.75	RT	-	12	-	-	-	-	-	-	-	-	-	2
14+65.97	12.75	RT TO	16+75.00	12.75	RT	-	208	-	-	-	-	-	-	-	-	-	35
16+75.00	12.75	RT TO	17+75.00	12.75	RT	-	99	-	-	-	-	-	-	-	-	-	16
17+75.00	12.75	RT TO	18+60.00	12.75	RT	-	84	-	-	-	-	-	-	-	-	-	14
18+60.00	12.75	RT TO	18+90.11	10.76	RT	-	27	-	-	-	-	-	-	-	-	-	7
18+81.18	35.93	RT TO	18+90.65	8.06	LT	-	-	-	-	-	-	-	32	-	-	-	-
18+81.41	35.31	RT TO				-	-	-	-	-	-	1	-	-	-	-	-
18+83.50	29.69	RT TO	18+89.78	12.82	RT	-	-	-	-	-	18	-	-	-	-	-	-
18+92.15	22.92	RT TO	19+43.34	24.69	RT	-	-	-	-	-	-	-	-	-	51	-	-
19+07.26	12.75	RT TO	18+90.11	10.76	RT	-	-	-	13	-	-	-	-	-	-	-	7
19+35.00	12.75	RT TO	19+07.26	12.75	RT	-	-	-	25	-	-	-	-	-	-	-	7
19+75.00	12.75	RT TO	19+35.00	12.75	RT	-	-	-	37	-	-	-	-	-	-	-	9
20+25.00	12.75	RT TO	19+75.00	12.75	RT	-	-	-	47	-	-	-	-	-	-	-	12
21+25.00	12.75	RT TO	20+25.00	12.75	RT	-	-	-	97	-	-	-	-	-	-	-	28
21+25.00	26.08	RT TO	21+25.00	12.75	RT	-	-	11	-	-	-	-	-	-	-	-	2
22+50.00	14.81	RT TO	21+25.00	12.75	RT	-	-	-	122	-	-	-	-	-	-	-	36
23+00.00	12.75	RT TO	22+50.00	14.81	RT	-	-	-	47	-	-	-	-	-	-	-	11
23+40.32	24.60	RT TO	23+49.58	24.37	RT	-	-	-	-	-	-	-	-	-	9	-	-
23+49.58	24.37	RT TO	23+00.00	12.75	RT	-	-	-	48	-	-	-	-	-	-	-	6
23+56.54	41.72	RT TO	23+49.58	24.37	RT	-	-	17	-	-	-	-	-	-	-	-	1
23+87.58	40.60	RT TO	23+94.03	23.54	RT	-	-	16	-	-	-	-	-	-	-	-	1
23+94.03	23.54	RT TO	24+02.98	23.96	RT	-	-	-	-	-	-	-	-	-	9	-	-
24+02.08	23.95	RT TO	23+94.03	23.54	RT	6	-	-	-	-	-	-	-	-	-	-	-
SUB-TOTAL:						6	483	203	288	368	1	18	1	32	217	355	281
TOTAL:						6	483	203	288	368	1	18	1	32	217	355	281